Ohio Department of Transportation
Official Bid Tabulation
Jack Marchbanks, Ph.D., Director

Project No. 220517
PID 91419
HAM-IR 74/IR 275-03.54/03.97
Federal
Type: FOUR LANE RESURFACING
Letting Date: 9/29/2022
Completion Date: 10/15/2023

Contract Awarded To: JOHN R JURGENSEN COMPANY
Award Amount: $7,995,513.28

Engineer's Estimate: $7,333,000.00

Bidder 1
JOHN R JURGENSEN COMPANY
11641 MOSTELLER RD
Hamilton
CINCINNATI, OH 45241
Bid $7,995,513.28

Bidder 2
BARRETT PAVING MATERIALS INC
3751 COMMERCE DR
Butler
MIDDLETOWN, OH 45055
Bid $8,845,989.00

Ref #1	**832E30000**	**EROSION CONTROL, (1000 EACH)**	
	Awd	$1.00	$1,000.00
	2	$1.00	$1,000.00

Section 1 - EROSION CONTROL - Totals

Awd	**$1,000.00**
2	**$1,000.00**

Ref #2	**253E02000**	**PAVEMENT REPAIR, (850 CY)**	
	Awd	$687.73	$584,570.50
	2	$700.00	$595,000.00
Ref #3	**254E01000**	**PAVEMENT PLANING, ASPHALT CONCRETE, 1.5", (410046 SY)**	
	Awd	$1.66	$680,676.36
	2	$2.15	$881,598.90
Ref #4	**254E01600**	**PATCHING PLANED SURFACE, (4108 SY)**	
	Awd	$6.71	$27,564.68
	2	$5.00	$20,540.00
Ref #5	**407E20000**	**NON-TRACKING TACK COAT, (36905 GAL)**	
	Awd	$5.00	$184,525.00
	2	$3.00	$110,715.00
Ref #6	**442E00100**	**ANTI-SEGREGATION EQUIPMENT, (10552 CY)**	
	Awd	$9.50	$100,244.00
	2	$16.00	$168,832.00
Ref #7	**442E10300**	**ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (, (16126 CY)**	
	Awd	$242.54	$3,911,200.04
	2	$250.00	$4,031,500.00
Ref #8	**442E10301**	**ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (, (960 CY)**	
	Awd	$297.93	$286,012.80
	2	$440.00	$422,400.00
Ref #9	**617E10100**	**COMPACTED AGGREGATE, (786 CY)**	
	Awd	$60.06	$47,207.16
	2	$120.00	$94,320.00
Ref #10	**617E20000**	**SHOULDER PREPARATION, (18855 SY)**	
	Awd	$1.49	$28,093.95
	2	$1.00	$18,855.00
Ref #11	**617E25000**	**WATER, (16 MGAL)**	
	Awd	$52.05	$832.80
	2	$50.00	$800.00
Ref #12	**618E40600**	**RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), (21.96 MILE)**	
	Awd	$885.00	$19,434.60
	2	$1,200.00	$26,352.00

Section 2 - PAVEMENT - Totals

Awd	**$5,870,361.89**
2	**$6,370,912.90**

Ref #13	**621E00100**	**RPM, (1241 EACH)**	
	Awd	$34.15	$42,380.15
	2	$31.50	$39,091.50

Ref #14	**621E54000**	**RAISED PAVEMENT MARKER REMOVED, (1241 EACH)**	
	Awd	$15.52	$19,260.32
	2	$10.00	$12,410.00
Ref #15	**644E00500**	**STOP LINE, (57 FT)**	
	Awd	$25.00	$1,425.00
	2	$25.00	$1,425.00
Ref #16	**644E00700**	**TRANSVERSE/DIAGONAL LINE, (11494 FT)**	
	Awd	$2.95	$33,907.30
	2	$2.95	$33,907.30
Ref #17	**644E00720**	**CHEVRON MARKING, (1053 FT)**	
	Awd	$2.95	$3,106.35
	2	$2.95	$3,106.35
Ref #18	**644E01300**	**LANE ARROW, (6 EACH)**	
	Awd	$980.00	$5,880.00
	2	$980.00	$5,880.00
Ref #19	**644E01360**	**WRONG WAY ARROW, (3 EACH)**	
	Awd	$1,500.00	$4,500.00
	2	$1,500.00	$4,500.00
Ref #20	**644E40000**	**SPEED MEASUREMENT MARKING, SPEED REDUCTION MARKING, (62 EACH)**	
	Awd	$390.00	$24,180.00
	2	$390.00	$24,180.00
Ref #21	**645E00116**	**EDGE LINE, 6", TYPE A3, (0.56 MILE)**	
	Awd	$30,945.00	$17,329.20
	2	$30,945.00	$17,329.20
Ref #22	**645E00216**	**LANE LINE, 6", TYPE A3, (0.28 MILE)**	
	Awd	$18,120.00	$5,073.60
	2	$18,120.00	$5,073.60
Ref #23	**807E14410**	**WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOT, (4768 FT)**	
	Awd	$2.00	$9,536.00
	2	$2.00	$9,536.00
Ref #24	**807E14010**	**WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDG, (32.14 MILE)**	
	Awd	$4,550.00	$146,237.00
	2	$4,550.00	$146,237.00
Ref #25	**807E14110**	**WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LAN, (17.66 MILE)**	
	Awd	$2,000.00	$35,320.00
	2	$2,000.00	$35,320.00
Ref #26	**807E14310**	**WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHA, (12909 FT)**	
	Awd	$2.85	$36,790.65
	2	$2.85	$36,790.65
Ref #27	**850E10010**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHAL, (49.8 MILE)**	
	Awd	$2,615.00	$130,227.00
	2	$2,615.00	$130,227.00
Ref #28	**850E10110**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHAL, (4768 FT)**	
	Awd	$1.25	$5,960.00
	2	$1.25	$5,960.00
Ref #29	**850E10130**	**GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHA, (12909 FT)**	
	Awd	$1.50	$19,363.50
	2	$1.50	$19,363.50

Ref #30	**850E20010**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRE, (0.84 MILE)**	
	Awd	$4,900.00	$4,116.00
	2	$4,900.00	$4,116.00

Section 3 - TRAFFIC CONTROL - Totals

Awd	**$544,592.07**
2	**$534,453.10**

Ref #31	**614E11110**	**LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSIST, (800 HOUR)**	
	Awd	$93.84	$75,072.00
	2	$85.00	$68,000.00
Ref #32	**614E12384**	**WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BI, (4 EACH)**	
	Awd	$2,264.97	$9,059.88
	2	$2,200.00	$8,800.00
Ref #33	**614E13310**	**BARRIER REFLECTOR, TYPE 1, ONE-WAY, (26 EACH)**	
	Awd	$23.12	$601.12
	2	$16.00	$416.00
Ref #34	**614E13350**	**OBJECT MARKER, ONE WAY, (26 EACH)**	
	Awd	$23.12	$601.12
	2	$17.00	$442.00
Ref #35	**614E18601**	**PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN, (6 SNMT)**	
	Awd	$995.00	$5,970.00
	2	$995.00	$5,970.00
Ref #36	**614E25620**	**WORK ZONE TRANSVERSE/DIAGONAL LINE, CLASS III, 642, (11494 FT)**	
	Awd	$1.35	$15,516.90
	2	$1.35	$15,516.90
Ref #37	**614E26610**	**WORK ZONE STOP LINE, CLASS III, 642 PAINT, (57 FT)**	
	Awd	$3.50	$199.50
	2	$3.50	$199.50
Ref #38	**614E30650**	**WORK ZONE ARROW, CLASS III, 642 PAINT, (6 EACH)**	
	Awd	$75.00	$450.00
	2	$75.00	$450.00
Ref #39	**614E30650**	**WORK ZONE ARROW, CLASS III, 642 PAINT, WRONG WAY, (3 EACH)**	
	Awd	$150.00	$450.00
	2	$150.00	$450.00
Ref #40	**614E98100**	**WORK ZONE PAVEMENT MARKING, MISC.: CHEVRON MARKING, (1693 FT)**	
	Awd	$1.35	$2,285.55
	2	$1.35	$2,285.55
Ref #41	**622E41100**	**PORTABLE BARRIER, UNANCHORED, (3500 FT)**	
	Awd	$17.78	$62,230.00
	2	$21.50	$75,250.00
Ref #42	**807E10010**	**WET REFLECTIVE TRAFFIC PAINT, EDGE LINE, 6", (32.14 MILE)**	
	Awd	$3,310.00	$106,383.40
	2	$3,310.00	$106,383.40
Ref #43	**807E10110**	**WET REFLECTIVE TRAFFIC PAINT, LANE LINE, 6", (17.66 MILE)**	
	Awd	$1,300.00	$22,958.00
	2	$1,300.00	$22,958.00

Ref #44	**807E10310**	**WET REFLECTIVE TRAFFIC PAINT, CHANNELIZING LINE, 1, (12909 FT)**	
	Awd	$2.00	$25,818.00
	2	$2.00	$25,818.00
Ref #45	**807E10410**	**WET REFLECTIVE TRAFFIC PAINT, DOTTED LINE, 6", (4768 FT)**	
	Awd	$2.00	$9,536.00
	2	$2.00	$9,536.00
Ref #46	**808E18700**	**DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY, (16 SNMT)**	
	Awd	$1,050.00	$16,800.00
	2	$1,050.00	$16,800.00

Section 4 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$353,931.47**
2	**$359,275.35**

Ref #47	**690E98400**	**SPECIAL - MISC.: WORK INVOLVING ASBESTOS CONTAINI, (LUMP SUM)**	
	Awd	$2,163.53	$2,163.53
	2	$2,000.00	$2,000.00

Section 5 - ENVIRONMENTAL / REMEDIATION - Totals

Awd	**$2,163.53**
2	**$2,000.00**

Ref #48	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$11,010.00	$11,010.00
	2	$32,000.00	$32,000.00
Ref #49	**511E34412**	**CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE, (3 CY)**	
	Awd	$5,025.00	$15,075.00
	2	$8,500.00	$25,500.00
Ref #50	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (32 SY)**	
	Awd	$44.57	$1,426.24
	2	$70.00	$2,240.00
Ref #51	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (1214 SY)**	
	Awd	$16.10	$19,545.40
	2	$16.50	$20,031.00
Ref #52	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (14 SY)**	
	Awd	$20.85	$291.90
	2	$55.00	$770.00
Ref #53	**519E11100**	**PATCHING CONCRETE STRUCTURE, (11 SF)**	
	Awd	$150.00	$1,650.00
	2	$850.00	$9,350.00
Ref #54	**519E12300**	**PATCHING CONCRETE BRIDGE DECK - TYPE B, (4 SY)**	
	Awd	$801.00	$3,204.00
	2	$1,100.00	$4,400.00
Ref #55	**530E00200**	**SPECIAL - STRUCTURES: CONSULTANT FOR CONCRETE QUAL, (LUMP SUM)**	
	Awd	$2,970.00	$2,970.00
	2	$3,750.00	$3,750.00

Section 6 - STRUCTURE REPAIR (HAM-74-0395L) - Totals

Awd	**$55,172.54**
2	**$98,041.00**

Ref #56	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (1214 SY)**	
	Awd	$16.10	$19,545.40
	2	$16.50	$20,031.00
Ref #57	**519E12300**	**PATCHING CONCRETE BRIDGE DECK - TYPE B, (7 SY)**	
	Awd	$801.00	$5,607.00
	2	$750.00	$5,250.00

Section 7 - STRUCTURE REPAIR (HAM-74-0395R) - Totals

Awd	**$25,152.40**
2	**$25,281.00**

Ref #58	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$7,410.00	$7,410.00
	2	$32,000.00	$32,000.00
Ref #59	**511E34412**	**CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE, (2 CY)**	
	Awd	$5,512.50	$11,025.00
	2	$8,500.00	$17,000.00
Ref #60	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (24 SY)**	
	Awd	$44.57	$1,069.68
	2	$70.00	$1,680.00
Ref #61	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (731 SY)**	
	Awd	$16.10	$11,769.10
	2	$16.50	$12,061.50
Ref #62	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (11 SY)**	
	Awd	$20.85	$229.35
	2	$55.00	$605.00
Ref #63	**530E00200**	**SPECIAL - STRUCTURES: CONSULTANT FOR CONCRETE QUAL, (LUMP SUM)**	
	Awd	$2,970.00	$2,970.00
	2	$2,000.00	$2,000.00

Section 8 - STRUCTURE REPAIR (HAM-74-0431L) - Totals

Awd	**$34,473.13**
2	**$65,346.50**

Ref #64	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$11,010.00	$11,010.00
	2	$32,000.00	$32,000.00
Ref #65	**511E34412**	**CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE, (3 CY)**	
	Awd	$5,025.00	$15,075.00
	2	$8,500.00	$25,500.00
Ref #66	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (14 SY)**	
	Awd	$44.57	$623.98
	2	$100.00	$1,400.00

Ref #67	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (731 SY)**	
	Awd	$16.10	$11,769.10
	2	$16.50	$12,061.50
Ref #68	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (7 SY)**	
	Awd	$20.85	$145.95
	2	$55.00	$385.00
Ref #69	**519E11100**	**PATCHING CONCRETE STRUCTURE, (10 SF)**	
	Awd	$150.00	$1,500.00
	2	$550.00	$5,500.00
Ref #70	**530E00200**	**SPECIAL - STRUCTURES: CONSULTANT FOR CONCRETE QUAL, (LUMP SUM)**	
	Awd	$2,970.00	$2,970.00
	2	$2,500.00	$2,500.00

Section 9 - STRUCTURE REPAIR (HAM-74-0431R) - Totals

Awd	**$43,094.03**
2	**$79,346.50**

Ref #71	**202E75266**	**VANDAL PROTECTION FENCE REMOVED AND RESET, (20 FT)**	
	Awd	$123.75	$2,475.00
	2	$285.00	$5,700.00
Ref #72	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (5 SY)**	
	Awd	$44.57	$222.85
	2	$150.00	$750.00
Ref #73	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (4 SY)**	
	Awd	$20.81	$83.24
	2	$55.00	$220.00
Ref #74	**519E11100**	**PATCHING CONCRETE STRUCTURE, (12 SF)**	
	Awd	$150.00	$1,800.00
	2	$1,500.00	$18,000.00

Section 10 - STRUCTURE REPAIR (HAM-74-0495) - Totals

Awd	**$4,581.09**
2	**$24,670.00**

Ref #75	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (10 SY)**	
	Awd	$44.57	$445.70
	2	$100.00	$1,000.00
Ref #76	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (1157 SY)**	
	Awd	$16.10	$18,627.70
	2	$16.50	$19,090.50
Ref #77	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (6 SY)**	
	Awd	$20.85	$125.10
	2	$55.00	$330.00
Ref #78	**513E21501**	**REPLACEMENT OF DETERIORATED END CROSSFRAMES, AS PE, (129 LB)**	
	Awd	$93.41	$12,049.89
	2	$45.00	$5,805.00
Ref #79	**514E00050**	**SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL, (20 SF)**	
	Awd	$120.00	$2,400.00
	2	$40.00	$800.00

Ref #80	**514E00056**	**FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME, (20 SF)**	
	Awd	$67.50	$1,350.00
	2	$40.00	$800.00
Ref #81	**514E00060**	**FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, (20 SF)**	
	Awd	$67.50	$1,350.00
	2	$150.00	$3,000.00
Ref #82	**514E00066**	**FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, (20 SF)**	
	Awd	$67.50	$1,350.00
	2	$150.00	$3,000.00
Ref #83	**514E10000**	**FINAL INSPECTION REPAIR, (1 EACH)**	
	Awd	$5,880.00	$5,880.00
	2	$150.00	$150.00
Ref #84	**519E11100**	**PATCHING CONCRETE STRUCTURE, (34 SF)**	
	Awd	$150.00	$5,100.00
	2	$275.00	$9,350.00
Ref #85	**519E12300**	**PATCHING CONCRETE BRIDGE DECK - TYPE B, (12 SY)**	
	Awd	$801.00	$9,612.00
	2	$750.00	$9,000.00

Section 11 - STRUCTURE REPAIR (HAM-74-0585L) - Totals

Awd	**$58,290.39**
2	**$52,325.50**

Ref #86	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (25 SY)**	
	Awd	$44.57	$1,114.25
	2	$75.00	$1,875.00
Ref #87	**512E10600**	**CONCRETE REPAIR BY EPOXY INJECTION, (4 FT)**	
	Awd	$787.50	$3,150.00
	2	$350.00	$1,400.00
Ref #88	**512E73500**	**TREATING CONCRETE BRIDGE DECKS WITH GRAVITY FED RE, (1502 SY)**	
	Awd	$16.10	$24,182.20
	2	$16.50	$24,783.00
Ref #89	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (16 SY)**	
	Awd	$20.85	$333.60
	2	$55.00	$880.00
Ref #90	**519E11100**	**PATCHING CONCRETE STRUCTURE, (92 SF)**	
	Awd	$150.00	$13,800.00
	2	$275.00	$25,300.00
Ref #91	**519E12300**	**PATCHING CONCRETE BRIDGE DECK - TYPE B, (8 SY)**	
	Awd	$801.00	$6,408.00
	2	$1,000.00	$8,000.00

Section 12 - STRUCTURE REPAIR (HAM-74-0585R) - Totals

Awd	**$48,988.05**
2	**$62,238.00**

Ref #92	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$28,775.66	$28,775.66
	2	$41,099.15	$41,099.15

Ref #93	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$717,801.29	$717,801.29
	2	$705,000.00	$705,000.00
Ref #94	**623E10001**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER P, (LUMP SUM)**	
	Awd	$7,135.74	$7,135.74
	2	$25,000.00	$25,000.00
Ref #95	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$200,000.00	$200,000.00
	2	$400,000.00	$400,000.00

Section 13 - INCIDENTALS - Totals

Awd	**$953,712.69**
2	**$1,171,099.15**