Ohio Department of Transportation
Official Bid Tabulation
Jack Marchbanks, Ph.D., Director

Project No. 230319
PID 115446
ROS-US 23-13.06
Non-Federal
Type: LIGHTING
Letting Date: 5/11/2023
Completion Date: 9/30/2023

Contract Awarded To: MILLER CABLE COMPANY
Award Amount: $646,500.00

Engineer's Estimate: $724,000.00

Bidder 1
MILLER CABLE COMPANY
210 S BROADWAY ST P O BOX 68
Seneca
GREEN SPRINGS, OH 44836
Bid $646,500.00

Bidder 2
COMPLETE GENERAL CONSTRUCTION COMPANY
1221 EAST FIFTH AVE
Franklin
COLUMBUS, OH 43219
Bid $787,059.70

Ref #1	**202E98700**	**ABANDON MISC.: LIGHTING CONDUIT/DUCT CABLE, (218 FT)**	
	Awd	$3.00	$654.00
	2	$30.00	$6,540.00

Section 1 - ROADWAY - Totals

Awd	**$654.00**
2	**$6,540.00**

Ref #2	**659E10000**	**SEEDING AND MULCHING, (6000 SY)**	
	Awd	$2.00	$12,000.00
	2	$1.05	$6,300.00
Ref #3	**659E20000**	**COMMERCIAL FERTILIZER, (0.5 TON)**	
	Awd	$500.00	$250.00
	2	$1,000.00	$500.00
Ref #4	**659E31000**	**LIME, (1.2 ACRE)**	
	Awd	$16.00	$19.20
	2	$200.00	$240.00
Ref #5	**659E35000**	**WATER, (16.2 MGAL)**	
	Awd	$1.00	$16.20
	2	$1.00	$16.20
Ref #6	**832E30000**	**EROSION CONTROL, (11282 EACH)**	
	Awd	$1.00	$11,282.00
	2	$1.00	$11,282.00

Section 2 - EROSION CONTROL - Totals

Awd	**$23,567.40**
2	**$18,338.20**

Ref #7	**625E00450**	**CONNECTION, FUSED PULL APART, (24 EACH)**	
	Awd	$105.00	$2,520.00
	2	$150.00	$3,600.00
Ref #8	**625E00480**	**CONNECTION, UNFUSED PERMANENT, (10 EACH)**	
	Awd	$105.00	$1,050.00
	2	$200.00	$2,000.00
Ref #9	**625E10494**	**LIGHT POLE, LOW MAST, ATLM50, (5 EACH)**	
	Awd	$3,500.00	$17,500.00
	2	$3,700.00	$18,500.00
Ref #10	**625E12200**	**LIGHT TOWER, BBB100, (1 EACH)**	
	Awd	$23,900.00	$23,900.00
	2	$29,000.00	$29,000.00
Ref #11	**625E13200**	**LIGHT TOWER, BBBB100, (2 EACH)**	
	Awd	$24,000.00	$48,000.00
	2	$29,000.00	$58,000.00
Ref #12	**625E13204**	**LIGHT TOWER, BBBB110, (3 EACH)**	
	Awd	$27,500.00	$82,500.00
	2	$34,000.00	$102,000.00
Ref #13	**625E13208**	**LIGHT TOWER, BBBB120, (3 EACH)**	
	Awd	$30,000.00	$90,000.00
	2	$37,000.00	$111,000.00

Ref #14	**625E14200**	**LIGHT POLE FOUNDATION, 24" X 10' DEEP, (5 EACH)**	
	Awd	$2,200.00	$11,000.00
	2	$1,725.00	$8,625.00
Ref #15	**625E15200**	**LIGHT TOWER FOUNDATION, 36" X 25' DEEP, (6 EACH)**	
	Awd	$8,750.00	$52,500.00
	2	$14,000.00	$84,000.00
Ref #16	**625E15400**	**LIGHT TOWER FOUNDATION, 42" X 25' DEEP, (3 EACH)**	
	Awd	$12,500.00	$37,500.00
	2	$23,000.00	$69,000.00
Ref #17	**625E23200**	**NO. 4 AWG 2400 VOLT DISTRIBUTION CABLE, (630 FT)**	
	Awd	$4.00	$2,520.00
	2	$4.00	$2,520.00
Ref #18	**625E23400**	**NO. 10 AWG POLE AND BRACKET CABLE, (600 FT)**	
	Awd	$2.00	$1,200.00
	2	$2.30	$1,380.00
Ref #19	**625E24320**	**1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 2400 VOLT C, (5530 FT)**	
	Awd	$11.00	$60,830.00
	2	$10.50	$58,065.00
Ref #20	**625E25500**	**CONDUIT, 3", 725.04, (100 FT)**	
	Awd	$26.00	$2,600.00
	2	$30.00	$3,000.00
Ref #21	**625E25904**	**CONDUIT, JACKED OR DRILLED, 725.05, 3", (81 FT)**	
	Awd	$37.00	$2,997.00
	2	$70.00	$5,670.00
Ref #22	**625E26261**	**LUMINAIRE, HIGH MAST, AS PER PLAN, SYMMETRIC, LED,, (35 EACH)**	
	Awd	$1,000.00	$35,000.00
	2	$1,270.00	$44,450.00
Ref #23	**625E26271**	**LUMINAIRE, LOW MAST, AS PER PLAN, SYMMETRIC, LED, , (5 EACH)**	
	Awd	$960.00	$4,800.00
	2	$1,240.00	$6,200.00
Ref #24	**625E29002**	**TRENCH, 24" DEEP, (5329 FT)**	
	Awd	$10.00	$53,290.00
	2	$6.00	$31,974.00
Ref #25	**625E30700**	**PULL BOX, 725.08, 18", (8 EACH)**	
	Awd	$900.00	$7,200.00
	2	$1,100.00	$8,800.00
Ref #26	**625E30706**	**PULL BOX, 725.08, 24", (1 EACH)**	
	Awd	$1,150.00	$1,150.00
	2	$1,350.00	$1,350.00
Ref #27	**625E31510**	**PULL BOX REMOVED, (7 EACH)**	
	Awd	$120.00	$840.00
	2	$525.00	$3,675.00
Ref #28	**625E32000**	**GROUND ROD, (23 EACH)**	
	Awd	$275.00	$6,325.00
	2	$500.00	$11,500.00
Ref #29	**625E34001**	**POWER SERVICE, AS PER PLAN, (1 EACH)**	
	Awd	$7,400.00	$7,400.00
	2	$13,500.00	$13,500.00

Ref #30	**625E36010**	**UNDERGROUND WARNING/MARKING TAPE, (5329 FT)**	
	Awd	$3.00	$15,987.00
	2	$2.50	$13,322.50
Ref #31	**625E75400**	**LIGHT POLE REMOVED, (8 EACH)**	
	Awd	$200.00	$1,600.00
	2	$500.00	$4,000.00
Ref #32	**625E75500**	**LIGHT POLE FOUNDATION REMOVED, (8 EACH)**	
	Awd	$200.00	$1,600.00
	2	$500.00	$4,000.00
Ref #33	**625E75506**	**LUMINAIRE REMOVED, (8 EACH)**	
	Awd	$50.00	$400.00
	2	$100.00	$800.00
Ref #34	**625E75510**	**POWER SERVICE REMOVED, (1 EACH)**	
	Awd	$500.00	$500.00
	2	$700.00	$700.00
Ref #35	**625E75800**	**DISCONNECT CIRCUIT, (1 EACH)**	
	Awd	$280.00	$280.00
	2	$350.00	$350.00
Ref #36	**625E98200**	**LIGHTING, MISC.: UNDERPASS LIGHTING, (LUMP SUM)**	
	Awd	$8,600.00	$8,600.00
	2	$17,000.00	$17,000.00

Section 3 - LIGHTING - Totals

Awd	**$581,589.00**
2	**$717,981.50**

Ref #37	**614E11110**	**LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSIST, (80 HOUR)**	
	Awd	$75.00	$6,000.00
	2	$90.00	$7,200.00

Section 4 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$6,000.00**
2	**$7,200.00**

Ref #38	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$5,954.60	$5,954.60
	2	$4,000.00	$4,000.00
Ref #39	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$3,250.00	$3,250.00
	2	$10,000.00	$10,000.00
Ref #40	**623E10000**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, (LUMP SUM)**	
	Awd	$5,485.00	$5,485.00
	2	$3,000.00	$3,000.00
Ref #41	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$20,000.00	$20,000.00
	2	$20,000.00	$20,000.00

Section 5 - INCIDENTALS - Totals

Awd	**$34,689.60**
2	**$37,000.00**