Ohio Department of Transportation
Official Bid Tabulation
Jack Marchbanks, Ph.D., Director

Project No. 230321
PID 116322
FRA-SR 161-15.80
Non-Federal
Type: MAJOR WIDENING
Letting Date: 5/25/2023
Completion Date: 8/1/2025

Contract Awarded To: KOKOSING CONSTRUCTION COMPANY INC
Award Amount: $65,596,371.08

Engineer's Estimate: $62,719,000.00

Bidder 1
KOKOSING CONSTRUCTION COMPANY INC
6235 WESTERVILLE RD
Franklin
WESTERVILLE, OH 43081
Bid $65,596,371.08

Ref #1	**201E11000**	**CLEARING AND GRUBBING, (LUMP SUM)**	
	Awd	$103,500.00	$103,500.00
Ref #2	**202E20010**	**HEADWALL REMOVED, (3 EACH)**	
	Awd	$400.00	$1,200.00
Ref #3	**202E23000**	**PAVEMENT REMOVED, (58217 SY)**	
	Awd	$13.00	$756,821.00
Ref #4	**202E30600**	**CONCRETE MEDIAN REMOVED, (43 SY)**	
	Awd	$22.00	$946.00
Ref #5	**202E30700**	**CONCRETE BARRIER REMOVED, (2984 FT)**	
	Awd	$30.00	$89,520.00
Ref #6	**202E32000**	**CURB REMOVED, (352 FT)**	
	Awd	$5.00	$1,760.00
Ref #7	**202E35100**	**PIPE REMOVED, 24" AND UNDER, (2997 FT)**	
	Awd	$30.00	$89,910.00
Ref #8	**202E35200**	**PIPE REMOVED, OVER 24", (1042 FT)**	
	Awd	$107.00	$111,494.00
Ref #9	**202E38000**	**GUARDRAIL REMOVED, (10185 FT)**	
	Awd	$2.00	$20,370.00
Ref #10	**202E38300**	**GUARDRAIL REMOVED, BARRIER DESIGN, (2010 FT)**	
	Awd	$4.00	$8,040.00
Ref #11	**202E42206**	**ANCHOR ASSEMBLY REMOVED, (42 EACH)**	
	Awd	$200.00	$8,400.00
Ref #12	**202E42210**	**ANCHOR ASSEMBLY REMOVED, BARRIER DESIGN, (13 EACH)**	
	Awd	$350.00	$4,550.00
Ref #13	**202E47000**	**BRIDGE TERMINAL ASSEMBLY REMOVED, (16 EACH)**	
	Awd	$100.00	$1,600.00
Ref #14	**202E47800**	**IMPACT ATTENUATOR REMOVED, (2 EACH)**	
	Awd	$500.00	$1,000.00
Ref #15	**202E48001**	**CABLE BARRIER REMOVED, AS PER PLAN, (18857 FT)**	
	Awd	$2.90	$54,685.30
Ref #16	**202E58000**	**MANHOLE REMOVED, (8 EACH)**	
	Awd	$800.00	$6,400.00
Ref #17	**202E58100**	**CATCH BASIN REMOVED, (46 EACH)**	
	Awd	$345.00	$15,870.00
Ref #18	**202E58200**	**INLET REMOVED, (3 EACH)**	
	Awd	$715.00	$2,145.00
Ref #19	**202E70110**	**SPECIAL - PIPE CLEANOUT, 24" AND UNDER, (500 FT)**	
	Awd	$4.75	$2,375.00
Ref #20	**202E70120**	**SPECIAL - PIPE CLEANOUT, 27" TO 48", (100 FT)**	
	Awd	$10.00	$1,000.00
Ref #21	**202E70130**	**SPECIAL - PIPE CLEANOUT OVER 48", (100 FT)**	
	Awd	$19.00	$1,900.00
Ref #22	**202E75000**	**FENCE REMOVED, (963 FT)**	
	Awd	$5.00	$4,815.00
Ref #23	**202E75711**	**SPECIAL - EXISTING CONDUIT CLEANED, AS PER PLAN, (1118 FT)**	
	Awd	$3.50	$3,913.00

Ref #24	**202E98100**	**REMOVAL MISC.: EX. TRAFFIC EQUIPMENT, (1 EACH)**	
	Awd	$2,800.00	$2,800.00
Ref #25	**202E98100**	**REMOVAL MISC.: INSPECTION WELL, (1 EACH)**	
	Awd	$500.00	$500.00
Ref #26	**202E98200**	**REMOVAL MISC.: CONDUIT, (50 FT)**	
	Awd	$59.00	$2,950.00
Ref #27	**202E98200**	**REMOVAL MISC.: FIBER OPTIC CABLE, (14301 FT)**	
	Awd	$1.55	$22,166.55
Ref #28	**202E98200**	**REMOVAL MISC.: SLOTTED DRAIN, (64 FT)**	
	Awd	$158.00	$10,112.00
Ref #29	**203E10000**	**EXCAVATION, (119811 CY)**	
	Awd	$19.00	$2,276,409.00
Ref #30	**203E20000**	**EMBANKMENT, (18223 CY)**	
	Awd	$4.60	$83,825.80
Ref #31	**203E20001**	**EMBANKMENT, AS PER PLAN, (5 CY)**	
	Awd	$170.00	$850.00
Ref #32	**204E10000**	**SUBGRADE COMPACTION, (121 SY)**	
	Awd	$15.00	$1,815.00
Ref #33	**204E45000**	**PROOF ROLLING, (2 HOUR)**	
	Awd	$215.00	$430.00
Ref #34	**209E15000**	**RESHAPING UNDER GUARDRAIL, (28 STA)**	
	Awd	$95.00	$2,660.00
Ref #35	**209E60200**	**LINEAR GRADING, (87 STA)**	
	Awd	$95.00	$8,265.00
Ref #36	**411E10000**	**STABILIZED CRUSHED AGGREGATE, (1605 CY)**	
	Awd	$50.00	$80,250.00
Ref #37	**606E15050**	**GUARDRAIL, TYPE MGS, (17766.5 FT)**	
	Awd	$20.50	$364,213.25
Ref #38	**606E15150**	**GUARDRAIL, TYPE MGS HALF POST SPACING, (175 FT)**	
	Awd	$32.00	$5,600.00
Ref #39	**606E15550**	**GUARDRAIL, BARRIER DESIGN, TYPE MGS, (536 FT)**	
	Awd	$36.00	$19,296.00
Ref #40	**606E26050**	**ANCHOR ASSEMBLY, MGS TYPE B, (1 EACH)**	
	Awd	$2,200.00	$2,200.00
Ref #41	**606E26150**	**ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016, (40 EACH)**	
	Awd	$2,500.00	$100,000.00
Ref #42	**606E26550**	**ANCHOR ASSEMBLY, MGS TYPE T, (28 EACH)**	
	Awd	$1,250.00	$35,000.00
Ref #43	**606E35002**	**MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, (20 EACH)**	
	Awd	$2,500.00	$50,000.00
Ref #44	**606E35006**	**MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1, BARRIER DESI, (2 EACH)**	
	Awd	$3,500.00	$7,000.00
Ref #45	**606E35102**	**MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2, (8 EACH)**	
	Awd	$300.00	$2,400.00
Ref #46	**606E60012**	**IMPACT ATTENUATOR, TYPE 1 (BIDIRECTIONAL), (1 EACH)**	
	Awd	$5,150.00	$5,150.00

Ref #47	**606E60022**	**IMPACT ATTENUATOR, TYPE 2 (UNIDIRECTIONAL) 60 MPH,, (1 EACH)**	
	Awd	$30,189.41	$30,189.41
Ref #48	**606E60022**	**IMPACT ATTENUATOR, TYPE 2 (UNIDIRECTIONAL) 70 MPH,, (1 EACH)**	
	Awd	$32,189.41	$32,189.41
Ref #49	**606E60028**	**IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL) 70 MPH, , (1 EACH)**	
	Awd	$32,223.37	$32,223.37
Ref #50	**607E23000**	**FENCE, TYPE CLT, (1000 FT)**	
	Awd	$28.50	$28,500.00
Ref #51	**607E35000**	**FENCE REMOVED AND REBUILT, (150 FT)**	
	Awd	$35.00	$5,250.00
Ref #52	**607E70000**	**FENCELINE SEEDING AND MULCHING, (966 FT)**	
	Awd	$0.80	$772.80
Ref #53	**622E10060**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE B, (3416 FT)**	
	Awd	$130.00	$444,080.00
Ref #54	**622E10061**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE B, AS PER PLA, (44 FT)**	
	Awd	$284.00	$12,496.00
Ref #55	**622E10120**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE C, (5644 FT)**	
	Awd	$145.00	$818,380.00
Ref #56	**622E10121**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE C, AS PER PLA, (458 FT)**	
	Awd	$245.00	$112,210.00
Ref #57	**622E10121**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE C, AS PER PLA, (60 FT)**	
	Awd	$223.00	$13,380.00
Ref #58	**622E10121**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE C, AS PER PLA, (13310 FT)**	
	Awd	$138.00	$1,836,780.00
Ref #59	**622E10140**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE C1, (120 FT)**	
	Awd	$465.00	$55,800.00
Ref #60	**622E10160**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE D, (988 FT)**	
	Awd	$150.00	$148,200.00
Ref #61	**622E10161**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE D, AS PER PLA, (25 FT)**	
	Awd	$190.00	$4,750.00
Ref #62	**622E10161**	**CONCRETE BARRIER, SINGLE SLOPE, TYPE D, AS PER PLA, (966 FT)**	
	Awd	$175.00	$169,050.00
Ref #63	**622E10200**	**BARRIER TRANSITION, (3 EACH)**	
	Awd	$5,930.00	$17,790.00
Ref #64	**622E24840**	**CONCRETE BARRIER END SECTION, TYPE B, (3 EACH)**	
	Awd	$8,880.00	$26,640.00
Ref #65	**622E24861**	**CONCRETE BARRIER END SECTION, TYPE C1, AS PER PLAN, (2 EACH)**	
	Awd	$8,560.00	$17,120.00
Ref #66	**622E25000**	**CONCRETE BARRIER END SECTION, TYPE D, (14 EACH)**	
	Awd	$3,500.00	$49,000.00
Ref #67	**622E25004**	**CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE , (13 EACH)**	
	Awd	$2,775.00	$36,075.00
Ref #68	**622E25008**	**CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE , (28 EACH)**	
	Awd	$3,215.00	$90,020.00
Ref #69	**622E25009**	**CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE , (36 EACH)**	
	Awd	$3,500.00	$126,000.00

Ref #70		**622E25014**	**CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE , (6 EACH)**	
		Awd	$5,500.00	$33,000.00
Ref #71		**622E25050**	**CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE , (24 EACH)**	
		Awd	$4,000.00	$96,000.00
Ref #72		**878E25000**	**INSPECTION AND COMPACTION TESTING OF UNBOUND MATER, (LUMP SUM)**	
		Awd	$95,000.00	$95,000.00

Section 1 - ROADWAY - Totals

Awd	**$8,707,002.89**

Ref #73	**AA1**	**204E10000**	**SUBGRADE COMPACTION (ALTERNATE 1), (69675 SY)**	
		Awd	$2.42	$168,613.50
Ref #74	**AA1**	**204E13000**	**EXCAVATION OF SUBGRADE (ALTERNATE 1), (18038 CY)**	
		Awd	$15.90	$286,804.20
Ref #75	**AA1**	**204E20000**	**EMBANKMENT (ALTERNATE 1), (18038 CY)**	
		Awd	$4.40	$79,367.20
Ref #76	**AA1**	**204E45000**	**PROOF ROLLING (ALTERNATE 1), (103 HOUR)**	
		Awd	$184.00	$18,952.00
Ref #77	**AA1**	**206E10500**	**CEMENT (ALTERNATE 1), (4130 TON)**	
		Awd	$275.00	$1,135,750.00
Ref #78	**AA1**	**206E11000**	**CURING COAT (ALTERNATE 1), (134732 SY)**	
		Awd	$1.42	$191,319.44
Ref #79	**AA1**	**206E15010**	**CEMENT STABILIZED SUBGRADE, 12 INCHES DEEP (ALTERN, (134732 SY)**	
		Awd	$5.00	$673,660.00

Section 2 - ROADWAY ALTERNATES - Totals

Awd	**$2,554,466.34**

Ref #86		**601E21000**	**CONCRETE SLOPE PROTECTION, (111 SY)**	
		Awd	$150.00	$16,650.00
Ref #87		**601E21050**	**TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT, (33 SY)**	
		Awd	$138.00	$4,554.00
Ref #88		**601E21060**	**TIED CONCRETE BLOCK MAT WITH TYPE 2 UNDERLAYMENT, (192 SY)**	
		Awd	$83.00	$15,936.00
Ref #89		**601E32200**	**ROCK CHANNEL PROTECTION, TYPE C WITH FILTER, (1 CY)**	
		Awd	$560.00	$560.00
Ref #90		**659E00100**	**SOIL ANALYSIS TEST, (2 EACH)**	
		Awd	$98.00	$196.00
Ref #91		**659E00300**	**TOPSOIL, (16061 CY)**	
		Awd	$9.00	$144,549.00
Ref #92		**659E10000**	**SEEDING AND MULCHING, (138222 SY)**	
		Awd	$0.65	$89,844.30
Ref #93		**659E14000**	**REPAIR SEEDING AND MULCHING, (6911 SY)**	
		Awd	$0.78	$5,390.58
Ref #94		**659E15000**	**INTER-SEEDING, (6911 SY)**	
		Awd	$0.78	$5,390.58

Ref #95	**659E20000**	**COMMERCIAL FERTILIZER, (19.28 TON)**	
	Awd	$825.45	$15,914.68
Ref #96	**659E31000**	**LIME, (28.56 ACRE)**	
	Awd	$157.10	$4,486.78
Ref #97	**659E35000**	**WATER, (1138 MGAL)**	
	Awd	$1.00	$1,138.00
Ref #98	**659E40000**	**MOWING, (933 MSF)**	
	Awd	$15.00	$13,995.00
Ref #99	**670E00500**	**SLOPE EROSION PROTECTION, (6315 SY)**	
	Awd	$1.37	$8,651.55
Ref #100	**670E00700**	**DITCH EROSION PROTECTION, (2731 SY)**	
	Awd	$1.49	$4,069.19
Ref #101	**670E00720**	**DITCH EROSION PROTECTION MAT, TYPE B, (5377 SY)**	
	Awd	$1.49	$8,011.73
Ref #102	**832E15000**	**STORM WATER POLLUTION PREVENTION PLAN, (LUMP SUM)**	
	Awd	$3,850.00	$3,850.00
Ref #103	**832E15002**	**STORM WATER POLLUTION PREVENTION INSPECTIONS, (LUMP SUM)**	
	Awd	$23,700.00	$23,700.00
Ref #104	**832E15010**	**STORM WATER POLLUTION PREVENTION INSPECTION SOFTWA, (LUMP SUM)**	
	Awd	$22,350.00	$22,350.00
Ref #105	**832E30000**	**EROSION CONTROL, (1409669 EACH)**	
	Awd	$1.00	$1,409,669.00
Ref #106	**836E10000**	**SEEDING AND EROSION CONTROL WITH TURF REINFORCING , (536 SY)**	
	Awd	$2.75	$1,474.00

Section 3 - EROSION CONTROL - Totals

Awd	**$1,800,380.39**

Ref #107	**602E20000**	**CONCRETE MASONRY, (21.2 CY)**	
	Awd	$1,600.00	$33,920.00
Ref #108	**605E11110**	**6" SHALLOW PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC, (69439 FT)**	
	Awd	$11.25	$781,188.75
Ref #109	**605E13300**	**6" UNCLASSIFIED PIPE UNDERDRAINS, (50 FT)**	
	Awd	$28.50	$1,425.00
Ref #110	**605E13410**	**6" UNCLASSIFIED PIPE UNDERDRAINS WITH GEOTEXTILE F, (6380 FT)**	
	Awd	$10.40	$66,352.00
Ref #111	**605E14020**	**6" BASE PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC, (62639 FT)**	
	Awd	$10.00	$626,390.00
Ref #112	**605E31100**	**AGGREGATE DRAINS, (265 FT)**	
	Awd	$22.00	$5,830.00
Ref #113	**611E00510**	**6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS, (2377 FT)**	
	Awd	$26.00	$61,802.00
Ref #114	**611E00900**	**6" CONDUIT, TYPE B, (5 FT)**	
	Awd	$203.00	$1,015.00
Ref #115	**611E01500**	**6" CONDUIT, TYPE F, (20 FT)**	
	Awd	$32.75	$655.00

Ref #116	**611E05900**	**15" CONDUIT, TYPE B, (2787 FT)**		
	Awd	$120.00	$334,440.00	
Ref #117	**611E05900**	**15" CONDUIT, TYPE B, 706.02, (162 FT)**		
	Awd	$120.00	$19,440.00	
Ref #118	**611E05900**	**15" CONDUIT, TYPE B, 707.33, (193 FT)**		
	Awd	$120.00	$23,160.00	
Ref #119	**611E06100**	**15" CONDUIT, TYPE C, (722 FT)**		
	Awd	$110.00	$79,420.00	
Ref #120	**611E06100**	**15" CONDUIT, TYPE C, 707.33, (49 FT)**		
	Awd	$110.00	$5,390.00	
Ref #121	**611E06700**	**15" CONDUIT, TYPE F, (171 FT)**		
	Awd	$95.00	$16,245.00	
Ref #122	**611E06700**	**15" CONDUIT, TYPE F, 707.33, (63 FT)**		
	Awd	$123.00	$7,749.00	
Ref #123	**611E07400**	**18" CONDUIT, TYPE B, (590 FT)**		
	Awd	$125.00	$73,750.00	
Ref #124	**611E07400**	**18" CONDUIT, TYPE B, 706.02, (185 FT)**		
	Awd	$125.00	$23,125.00	
Ref #125	**611E07400**	**18" CONDUIT, TYPE B, 707.33, (58 FT)**		
	Awd	$160.00	$9,280.00	
Ref #126	**611E07600**	**18" CONDUIT, TYPE C, (659 FT)**		
	Awd	$115.00	$75,785.00	
Ref #127	**611E07600**	**18" CONDUIT, TYPE C, 706.02, (23 FT)**		
	Awd	$150.00	$3,450.00	
Ref #128	**611E07600**	**18" CONDUIT, TYPE C, 707.33, (19 FT)**		
	Awd	$165.00	$3,135.00	
Ref #129	**611E08900**	**21" CONDUIT, TYPE B, (40 FT)**		
	Awd	$280.00	$11,200.00	
Ref #130	**611E10400**	**24" CONDUIT, TYPE B, (10 FT)**		
	Awd	$340.00	$3,400.00	
Ref #131	**611E10400**	**24" CONDUIT, TYPE B, 707.33, (10 FT)**		
	Awd	$260.00	$2,600.00	
Ref #132	**611E10600**	**24" CONDUIT, TYPE C, (609 FT)**		
	Awd	$143.00	$87,087.00	
Ref #133	**611E10600**	**24" CONDUIT, TYPE C, 707.33, (5 FT)**		
	Awd	$357.00	$1,785.00	
Ref #134	**611E13600**	**30" CONDUIT, TYPE C, (601 FT)**		
	Awd	$157.00	$94,357.00	
Ref #135	**611E13600**	**30" CONDUIT, TYPE C, 706.02, (55 FT)**		
	Awd	$248.00	$13,640.00	
Ref #136	**611E16400**	**36" CONDUIT, TYPE B, 706.02, (86 FT)**		
	Awd	$330.00	$28,380.00	
Ref #137	**611E16600**	**36" CONDUIT, TYPE C, 706.02, (53 FT)**		
	Awd	$300.00	$15,900.00	
Ref #138	**611E20900**	**48" CONDUIT, TYPE B, (15 FT)**		
	Awd	$353.00	$5,295.00	

Ref #139	**611E20900**	**48" CONDUIT, TYPE B, 706.02, (9 FT)**		
	Awd	$610.00	$5,490.00	
Ref #140	**611E21100**	**48" CONDUIT, TYPE C, (236 FT)**		
	Awd	$276.00	$65,136.00	
Ref #141	**611E21100**	**48" CONDUIT, TYPE C, 706.02, (20 FT)**		
	Awd	$490.00	$9,800.00	
Ref #142	**611E23800**	**60" CONDUIT, TYPE B, 706.02, (381 FT)**		
	Awd	$690.00	$262,890.00	
Ref #143	**611E97400**	**CONDUIT, MISC.: TYPE B FOR DRAINAGE DISCHARGE CONT, (50 FT)**		
	Awd	$107.00	$5,350.00	
Ref #144	**611E97400**	**CONDUIT, MISC.: TYPE C FOR DRAINAGE DISCHARGE CONT, (50 FT)**		
	Awd	$89.00	$4,450.00	
Ref #145	**611E97400**	**CONDUIT, MISC.: TYPE E FOR DRAINAGE DISCHARGE CONT, (25 FT)**		
	Awd	$92.00	$2,300.00	
Ref #146	**611E97400**	**CONDUIT, MISC.: TYPE F FOR DRAINAGE DISCHARGE CONT, (25 FT)**		
	Awd	$111.00	$2,775.00	
Ref #147	**611E98180**	**CATCH BASIN, NO. 3A, (4 EACH)**		
	Awd	$3,700.00	$14,800.00	
Ref #148	**611E98230**	**CATCH BASIN, NO. 4, (3 EACH)**		
	Awd	$7,030.00	$21,090.00	
Ref #149	**611E98300**	**CATCH BASIN, NO. 5, (30 EACH)**		
	Awd	$6,280.00	$188,400.00	
Ref #150	**611E98341**	**CATCH BASIN, NO. 5A, (6 EACH)**		
	Awd	$12,830.00	$76,980.00	
Ref #151	**611E98370**	**CATCH BASIN, NO. 6, (6 EACH)**		
	Awd	$3,530.00	$21,180.00	
Ref #152	**611E98410**	**CATCH BASIN, NO. 8, (3 EACH)**		
	Awd	$7,450.00	$22,350.00	
Ref #153	**611E98470**	**CATCH BASIN, NO. 2-2B, (1 EACH)**		
	Awd	$2,700.00	$2,700.00	
Ref #154	**611E98630**	**CATCH BASIN ADJUSTED TO GRADE, (2 EACH)**		
	Awd	$870.00	$1,740.00	
Ref #155	**611E98800**	**INLET, NO. 3B, (9 EACH)**		
	Awd	$11,775.00	$105,975.00	
Ref #156	**611E98801**	**INLET, NO. 3B, AS PER PLAN, (5 EACH)**		
	Awd	$11,700.00	$58,500.00	
Ref #157	**611E98810**	**INLET, NO. 3C, (2 EACH)**		
	Awd	$12,300.00	$24,600.00	
Ref #158	**611E98811**	**INLET, NO. 3C, AS PER PLAN, (21 EACH)**		
	Awd	$12,660.00	$265,860.00	
Ref #159	**611E98820**	**INLET, NO. 3D, (2 EACH)**		
	Awd	$11,190.00	$22,380.00	
Ref #160	**611E99104**	**INLET, NO. 3 FOR SINGLE SLOPE BARRIER, TYPE C, (2 EACH)**		
	Awd	$12,170.00	$24,340.00	
Ref #161	**611E99110**	**INLET, NO. 3 FOR SINGLE SLOPE BARRIER, TYPE C1, (2 EACH)**		
	Awd	$15,000.00	$30,000.00	

Ref #162	**611E99114**	**INLET, NO. 3 FOR SINGLE SLOPE BARRIER, TYPE D, (2 EACH)**	
	Awd	$10,900.00	$21,800.00
Ref #163	**611E99150**	**INLET ADJUSTED TO GRADE, (7 EACH)**	
	Awd	$1,345.00	$9,415.00
Ref #164	**611E99574**	**MANHOLE, NO. 3, (13 EACH)**	
	Awd	$6,100.00	$79,300.00
Ref #165	**611E99651**	**MANHOLE FRAME AND COVER, AS PER PLAN - BOLT DOWN L, (1 EACH)**	
	Awd	$790.00	$790.00
Ref #166	**611E99660**	**MANHOLE RECONSTRUCTED TO GRADE, (22 EACH)**	
	Awd	$1,900.00	$41,800.00
Ref #167	**611E99710**	**PRECAST REINFORCED CONCRETE OUTLET, (17 EACH)**	
	Awd	$423.35	$7,196.95
Ref #168	**611E99720**	**INSPECTION WELL, (1 EACH)**	
	Awd	$3,600.00	$3,600.00
Ref #169	**611E99820**	**SPECIAL - MISCELLANEOUS METAL, (2750 LB)**	
	Awd	$2.92	$8,030.00
Ref #170	**839E29000**	**TRENCH DRAIN, TYPE A WITH STANDARD GRATE, (263 FT)**	
	Awd	$275.00	$72,325.00

Section 4 - DRAINAGE - Totals

Awd	**$3,999,933.70**

Ref #171	**251E01000**	**PARTIAL DEPTH PAVEMENT REPAIR (441), (610 SY)**	
	Awd	$100.00	$61,000.00
Ref #172	**253E90100**	**PAVEMENT REPAIR, MISC.: HAMILTON RD. REPAIR, (1000 SY)**	
	Awd	$200.00	$200,000.00
Ref #173	**253E90100**	**PAVEMENT REPAIR, MISC.: US 62 REPAIR, (1000 SY)**	
	Awd	$250.00	$250,000.00
Ref #174	**254E01000**	**PAVEMENT PLANING, ASPHALT CONCRETE, 1.5", (389386 SY)**	
	Awd	$3.00	$1,168,158.00
Ref #175	**254E01000**	**PAVEMENT PLANING, ASPHALT CONCRETE, VARIABLE DEPTH, (24730 SY)**	
	Awd	$12.00	$296,760.00
Ref #176	**254E01011**	**PAVEMENT PLANING, PORTLAND CEMENT CONCRETE, AS PER, (106 SY)**	
	Awd	$75.00	$7,950.00
Ref #177	**302E56000**	**ASPHALT CONCRETE BASE, PG64-22, (449), (38016 CY)**	
	Awd	$170.00	$6,462,720.00
Ref #178	**304E20000**	**AGGREGATE BASE, (54513 CY)**	
	Awd	$60.00	$3,270,780.00
Ref #179	**305E13010**	**9" CONCRETE BASE, CLASS QC 1P, (24 SY)**	
	Awd	$113.00	$2,712.00
Ref #180	**407E20000**	**NON-TRACKING TACK COAT, (58174 GAL)**	
	Awd	$2.75	$159,978.50
Ref #181	**441E10100**	**ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG, (220 CY)**	
	Awd	$425.00	$93,500.00
Ref #182	**441E50000**	**ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG, (2 CY)**	
	Awd	$2,000.00	$4,000.00

Ref #183	**441E50200**	**ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448, (3 CY)**	
	Awd	$1,500.00	$4,500.00
Ref #184	**442E00100**	**ANTI-SEGREGATION EQUIPMENT, (17130 CY)**	
	Awd	$1.00	$17,130.00
Ref #185	**442E10001**	**ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (, (24503 CY)**	
	Awd	$310.00	$7,595,930.00
Ref #186	**442E10001**	**ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (, (813 CY)**	
	Awd	$350.00	$284,550.00
Ref #187	**442E10080**	**ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYP, (10381 CY)**	
	Awd	$300.00	$3,114,300.00
Ref #188	**452E13011**	**9" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, , (841 SY)**	
	Awd	$100.00	$84,100.00
Ref #189	**609E24510**	**CURB, TYPE 4-C, (364 FT)**	
	Awd	$40.00	$14,560.00
Ref #190	**609E26000**	**CURB, TYPE 6, (403 FT)**	
	Awd	$31.00	$12,493.00
Ref #191	**609E71000**	**CONCRETE MEDIAN, 6", (385 SF)**	
	Awd	$10.00	$3,850.00
Ref #192	**690E98700**	**SPECIAL - QC 1 CONCRETE PER C&MS 499, (42 CY)**	
	Awd	$322.00	$13,524.00
Ref #193	**872E10000**	**VOID REDUCING ASPHALT MEMBRANE (VRAM), (276807 FT)**	
	Awd	$1.86	$514,861.02
Ref #194	**889E10000**	**LONGITUDINAL DIAMOND GROOVING., (2848 SY)**	
	Awd	$3.98	$11,335.04

Section 5 - PAVEMENT - Totals

Awd	**$23,648,691.56**

Ref #195	**638E01205**	**8" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, PUS, (230 FT)**	
	Awd	$144.00	$33,120.00
Ref #196	**638E07303**	**18" STEEL PIPE ENCASEMENT, BORED OR JACKED, AS PER, (112 FT)**	
	Awd	$890.00	$99,680.00

Section 6 - WATER WORK - Totals

Awd	**$132,800.00**

Ref #197	**625E00480**	**CONNECTION, UNFUSED PERMANENT, (11 EACH)**	
	Awd	$121.00	$1,331.00
Ref #198	**625E10494**	**LIGHT POLE, LOW MAST: ALMB50, (112 EACH)**	
	Awd	$3,600.00	$403,200.00
Ref #199	**625E14307**	**MEDIAN LIGHT POLE FOUNDATION, 10' DEEP, AS PER PLA, (109 EACH)**	
	Awd	$9,800.00	$1,068,200.00
Ref #200	**625E14307**	**MEDIAN LIGHT POLE FOUNDATION, 10' DEEP, AS PER PLA, (2 EACH)**	
	Awd	$7,670.00	$15,340.00
Ref #201	**625E14307**	**MEDIAN LIGHT POLE FOUNDATION, 10' DEEP, AS PER PLA, (1 EACH)**	
	Awd	$6,230.00	$6,230.00

Ref #202	**625E15100**	**LIGHT TOWER FOUNDATION, 36" X 20' DEEP, (2 EACH)**	
	Awd	$9,040.00	$18,080.00
Ref #203	**625E15200**	**LIGHT TOWER FOUNDATION, 36" X 25' DEEP, (2 EACH)**	
	Awd	$10,920.00	$21,840.00
Ref #204	**625E23300**	**NO. 2 AWG 2400 VOLT DISTRIBUTION CABLE, (1630 FT)**	
	Awd	$5.50	$8,965.00
Ref #205	**625E24320**	**1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 2400 VOLT C, (1421 FT)**	
	Awd	$12.40	$17,620.40
Ref #206	**625E26273**	**LUMINAIRE, LOW MAST, SOLID STATE (LED), AS PER PLA, (112 EACH)**	
	Awd	$2,045.00	$229,040.00
Ref #207	**625E29002**	**TRENCH, 24" DEEP, (1361 FT)**	
	Awd	$8.30	$11,296.30
Ref #208	**625E29900**	**JUNCTION BOX, (5 EACH)**	
	Awd	$1,870.00	$9,350.00
Ref #209	**625E29910**	**TRANSITION JUNCTION BOX, (6 EACH)**	
	Awd	$1,910.00	$11,460.00
Ref #210	**625E30700**	**PULL BOX, 725.08, 18", (1 EACH)**	
	Awd	$1,630.00	$1,630.00
Ref #211	**625E32000**	**GROUND ROD, (8 EACH)**	
	Awd	$206.00	$1,648.00
Ref #212	**625E33000**	**STRUCTURE GROUNDING SYSTEM, (3 EACH)**	
	Awd	$5,950.00	$17,850.00
Ref #213	**625E35021**	**RE-ERECT EXISTING LIGHT TOWER, AS PER PLAN, (4 EACH)**	
	Awd	$4,175.00	$16,700.00
Ref #214	**625E37101**	**SERVICE TO UNDERPASS LIGHTING, AS PER PLAN, (2 EACH)**	
	Awd	$4,000.00	$8,000.00
Ref #215	**625E39520**	**PULL BOX CLEANED, (2 EACH)**	
	Awd	$99.00	$198.00
Ref #216	**625E40000**	**SPECIAL - MAINTAIN EXISTING LIGHTING, (LUMP SUM)**	
	Awd	$11,100.00	$11,100.00
Ref #217	**625E75540**	**LIGHT TOWER FOUNDATION REMOVED, (4 EACH)**	
	Awd	$275.00	$1,100.00
Ref #218	**625E75800**	**DISCONNECT CIRCUIT, (3 EACH)**	
	Awd	$120.00	$360.00
Ref #219	**625E98000**	**LIGHTING, MISC.: AEP POWER SERVICE, CITY OF COLUMB, (3 EACH)**	
	Awd	$9,000.00	$27,000.00
Ref #220	**625E98000**	**LIGHTING, MISC.: AEP POWER SERVICE, CITY OF NEW AL, (2 EACH)**	
	Awd	$10,440.00	$20,880.00
Ref #221	**625E98000**	**LIGHTING, MISC.:CITY, 3 WIRE, 480V, PAD MOUNT (MIS, (5 EACH)**	
	Awd	$4,970.00	$24,850.00
Ref #222	**625E98000**	**LIGHTING, MISC.:CITY, FOUNDATION REMOVAL (MIS-900), (45 EACH)**	
	Awd	$250.00	$11,250.00
Ref #223	**625E98000**	**LIGHTING, MISC.:CITY, FOUNDATION, 6' (MIS 201), (26 EACH)**	
	Awd	$2,160.00	$56,160.00
Ref #224	**625E98000**	**LIGHTING, MISC.:CITY, FOUNDATION, 8' (MIS 201), (65 EACH)**	
	Awd	$2,287.68	$148,699.20

Ref #225	**625E98000**	**LIGHTING, MISC.:CITY, LUMINAIRE, LED, COBRA HEAD, , (9 EACH)**	
	Awd	$645.00	$5,805.00
Ref #226	**625E98000**	**LIGHTING, MISC.:CITY, LUMINAIRE, LED, COBRA HEAD, , (65 EACH)**	
	Awd	$750.00	$48,750.00
Ref #227	**625E98000**	**LIGHTING, MISC.:CITY, LUMINAIRE, LED, TEAR DROP (M, (17 EACH)**	
	Awd	$2,200.00	$37,400.00
Ref #228	**625E98000**	**LIGHTING, MISC.:CITY, LUMINAIRE, LED, UNDERPASS (M, (4 EACH)**	
	Awd	$1,610.00	$6,440.00
Ref #229	**625E98000**	**LIGHTING, MISC.:CITY, POLE TO BE WIRED, 2-WIRE (MI, (40 EACH)**	
	Awd	$290.00	$11,600.00
Ref #230	**625E98000**	**LIGHTING, MISC.:CITY, POLE TO BE WIRED, 3-WIRE (MI, (168 EACH)**	
	Awd	$275.00	$46,200.00
Ref #231	**625E98000**	**LIGHTING, MISC.:CITY, POLE, 15' BRACKET, T-BASE, 3, (4 EACH)**	
	Awd	$3,310.00	$13,240.00
Ref #232	**625E98000**	**LIGHTING, MISC.:CITY, POLE, 15' BRACKET, T-BASE, 4, (65 EACH)**	
	Awd	$3,940.00	$256,100.00
Ref #233	**625E98000**	**LIGHTING, MISC.:CITY, POLE, 8' BRACKET, T-BASE, 30, (5 EACH)**	
	Awd	$3,130.00	$15,650.00
Ref #234	**625E98000**	**LIGHTING, MISC.:CITY, POLE, BLACK/GREEN TEAR DROP , (17 EACH)**	
	Awd	$3,630.00	$61,710.00
Ref #235	**625E98000**	**LIGHTING, MISC.:CITY, PULL BOX, MIS 54, (20 EACH)**	
	Awd	$1,115.00	$22,300.00
Ref #236	**625E98000**	**LIGHTING, MISC.:CITY, PULL BOX, SPECIAL, 17"X30"X2, (16 EACH)**	
	Awd	$1,610.00	$25,760.00
Ref #237	**625E98000**	**LIGHTING, MISC.:CT METER CABINET, 480V, AEP POWERE, (5 EACH)**	
	Awd	$8,100.00	$40,500.00
Ref #238	**625E98100**	**LIGHTING, MISC.:'CITY, 2" CONDUIT, CONCRETE ENCASE, (14968 FT)**	
	Awd	$26.00	$389,168.00
Ref #239	**625E98100**	**LIGHTING, MISC.:'CITY, 3" CONDUIT-JACKING OR DRILL, (1090 FT)**	
	Awd	$129.00	$140,610.00
Ref #240	**625E98100**	**LIGHTING, MISC.:CITY, CONDUIT REPAIR (MIS-706), (5 FT)**	
	Awd	$320.00	$1,600.00
Ref #241	**625E98100**	**LIGHTING, MISC.:CITY, UNDERGROUND CIRCUIT, 2-WIRE , (6482 FT)**	
	Awd	$6.60	$42,781.20
Ref #242	**625E98100**	**LIGHTING, MISC.:CITY, UNDERGROUND CIRCUIT, 3-WIRE , (39178 FT)**	
	Awd	$7.55	$295,793.90
Ref #243	**625E98200**	**LIGHTING, MISC.:CITY OF COLUMBUS, UNDERGROUND SYST, (LUMP SUM)**	
	Awd	$62,100.00	$62,100.00
Ref #244	**625E98200**	**LIGHTING, MISC.:MAINTAIN EXISTING LIGHTING, CITY O, (LUMP SUM)**	
	Awd	$105,000.00	$105,000.00
Ref #245	**625E98200**	**LIGHTING, MISC.:MAINTAIN EXISTING LIGHTING, CITY O, (LUMP SUM)**	
	Awd	$29,000.00	$29,000.00
Ref #246	**625E98200**	**LIGHTING, MISC.:POLE IDENTIFICATION TAG INSTALLATI, (LUMP SUM)**	
	Awd	$12,400.00	$12,400.00
Ref #701	**625E98200**	**LIGHTING, MISC.: CITY OF NEW ALBANY, UNDERGROUND S, (LUMP SUM)**	
	Awd	$15,800.00	$15,800.00

Section 7 - LIGHTING - Totals

Awd		**$3,855,086.00**

Ref #247	**620E00500**	**DELINEATOR, POST GROUND MOUNTED, (103 EACH)**		
	Awd	$75.00	$7,725.00	
Ref #248	**621E00100**	**RPM, (2212 EACH)**		
	Awd	$35.05	$77,530.60	
Ref #249	**621E54000**	**RAISED PAVEMENT MARKER REMOVED, (2069 EACH)**		
	Awd	$10.19	$21,083.11	
Ref #250	**625E32000**	**GROUND ROD, (42 EACH)**		
	Awd	$350.00	$14,700.00	
Ref #251	**626E00102**	**BARRIER REFLECTOR, TYPE 1 (BI-DIRECTIONAL), (491 EACH)**		
	Awd	$12.00	$5,892.00	
Ref #252	**626E00102**	**BARRIER REFLECTOR, TYPE 1 (ONE WAY), (739 EACH)**		
	Awd	$11.00	$8,129.00	
Ref #253	**626E00110**	**BARRIER REFLECTOR, TYPE 2 (BI-DIRECTIONAL), (36 EACH)**		
	Awd	$10.00	$360.00	
Ref #254	**626E00110**	**BARRIER REFLECTOR, TYPE 2 (ONE WAY), (164 EACH)**		
	Awd	$9.50	$1,558.00	
Ref #255	**626E00116**	**BARRIER REFLECTOR, TYPE 5 (BI-DIRECTIONAL), (7 EACH)**		
	Awd	$16.00	$112.00	
Ref #256	**626E00116**	**BARRIER REFLECTOR, TYPE 5 (ONE WAY), (204 EACH)**		
	Awd	$15.00	$3,060.00	
Ref #257	**630E03100**	**GROUND MOUNTED SUPPORT, NO. 3 POST, (1424.5 FT)**		
	Awd	$13.00	$18,518.50	
Ref #258	**630E04100**	**GROUND MOUNTED SUPPORT, NO. 4 POST, (64 FT)**		
	Awd	$17.50	$1,120.00	
Ref #259	**630E06400**	**GROUND MOUNTED STRUCTURAL BEAM SUPPORT, S4X7.7, (38.8 FT)**		
	Awd	$17.50	$679.00	
Ref #260	**630E07000**	**GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W8X18, (21 FT)**		
	Awd	$40.00	$840.00	
Ref #261	**630E07600**	**GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W10X12, (44.8 FT)**		
	Awd	$26.00	$1,164.80	
Ref #262	**630E08000**	**GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W12X30, (51.8 FT)**		
	Awd	$62.00	$3,211.60	
Ref #263	**630E08200**	**GROUND MOUNTED SUPPORT, PIPE, (8 EACH)**		
	Awd	$1,000.00	$8,000.00	
Ref #264	**630E08600**	**SIGN POST REFLECTOR, (14 EACH)**		
	Awd	$42.00	$588.00	
Ref #265	**630E09000**	**BREAKAWAY STRUCTURAL BEAM CONNECTION, (4 EACH)**		
	Awd	$675.00	$2,700.00	
Ref #266	**630E72320**	**OVERHEAD SIGN SUPPORT, TYPE TC-12.31, DESIGN 6, (11 EACH)**		
	Awd	$25,000.00	$275,000.00	
Ref #267	**630E72330**	**OVERHEAD SIGN SUPPORT, TYPE TC-12.31, DESIGN 10, (4 EACH)**		
	Awd	$34,000.00	$136,000.00	

Ref #268	**630E72340**	**OVERHEAD SIGN SUPPORT, TYPE TC-12.31, DESIGN 12, (9 EACH)**	
	Awd	$37,500.00	$337,500.00
Ref #269	**630E72410**	**OVERHEAD SIGN SUPPORT, TYPE TC-15.116, DESIGN 1, (1 EACH)**	
	Awd	$70,500.00	$70,500.00
Ref #270	**630E72420**	**OVERHEAD SIGN SUPPORT, TYPE TC-15.116, DESIGN 2, (8 EACH)**	
	Awd	$97,500.00	$780,000.00
Ref #271	**630E79611**	**SIGN SUPPORT ASSEMBLY, BARRIER MOUNTED, AS PER PLA, (2 EACH)**	
	Awd	$1,250.00	$2,500.00
Ref #272	**630E80100**	**SIGN, FLAT SHEET, (1290.8 SF)**	
	Awd	$17.50	$22,589.00
Ref #273	**630E80200**	**SIGN, GROUND MOUNTED EXTRUSHEET, (596 SF)**	
	Awd	$22.00	$13,112.00
Ref #274	**630E80224**	**SIGN, OVERHEAD EXTRUSHEET, (8629 SF)**	
	Awd	$22.00	$189,838.00
Ref #275	**630E84010**	**CONCRETE BARRIER MEDIAN OVERHEAD SIGN SUPPORT FOUN, (14 EACH)**	
	Awd	$12,700.00	$177,800.00
Ref #276	**630E84500**	**GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION, (10 EACH)**	
	Awd	$1,200.00	$12,000.00
Ref #277	**630E84510**	**RIGID OVERHEAD SIGN SUPPORT FOUNDATION, (26 EACH)**	
	Awd	$10,000.00	$260,000.00
Ref #278	**630E84511**	**RIGID OVERHEAD SIGN SUPPORT FOUNDATION, AS PER PLA, (2 EACH)**	
	Awd	$22,500.00	$45,000.00
Ref #279	**630E84900**	**REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL, (110 EACH)**	
	Awd	$15.00	$1,650.00
Ref #280	**630E85100**	**REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, (2 EACH)**	
	Awd	$125.00	$250.00
Ref #281	**630E85400**	**REMOVAL OF GROUND MOUNTED MAJOR SIGN AND DISPOSAL, (33 EACH)**	
	Awd	$200.00	$6,600.00
Ref #282	**630E86002**	**REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSA, (111 EACH)**	
	Awd	$18.00	$1,998.00
Ref #283	**630E86102**	**REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT , (42 EACH)**	
	Awd	$350.00	$14,700.00
Ref #284	**630E86272**	**REMOVAL OF GROUND MOUNTED PIPE SUPPORT AND DISPOSA, (9 EACH)**	
	Awd	$350.00	$3,150.00
Ref #285	**630E87400**	**REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL, (50 EACH)**	
	Awd	$350.00	$17,500.00
Ref #286	**630E89100**	**REMOVAL OF OVERHEAD SIGN SUPPORT AND REERECTION, T, (1 EACH)**	
	Awd	$5,000.00	$5,000.00
Ref #287	**630E89706**	**REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYP, (15 EACH)**	
	Awd	$2,150.00	$32,250.00
Ref #288	**630E89804**	**REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYP, (11 EACH)**	
	Awd	$3,500.00	$38,500.00
Ref #289	**630E97700**	**SIGNING, MISC.: SAFE SIGN BREAKAWAY SYSTEM, (1 EACH)**	
	Awd	$3,000.00	$3,000.00
Ref #290	**631E94490**	**REMOVAL, MISC.: DYNAMIC MESSAGE SIGN, (3 EACH)**	
	Awd	$600.00	$1,800.00

Ref #291	**644E00720**	**CHEVRON MARKING, (271 FT)**		
	Awd	$10.00	$2,710.00	
Ref #292	**644E01350**	**LANE REDUCTION ARROW, (13 EACH)**		
	Awd	$390.00	$5,070.00	
Ref #293	**644E01410**	**WORD ON PAVEMENT, 96", (2 EACH)**		
	Awd	$165.00	$330.00	
Ref #294	**644E50100**	**PAVEMENT MARKING, MISC.: LANE ARROW, 72", (8 EACH)**		
	Awd	$130.00	$1,040.00	
Ref #295	**644E50300**	**PAVEMENT MARKING, MISC.: CHANNELIZING LINE, 10", W, (1219 FT)**		
	Awd	$2.50	$3,047.50	
Ref #296	**644E50300**	**PAVEMENT MARKING, MISC.: EDGE LINE, 5", WHITE, (1343 FT)**		
	Awd	$1.75	$2,350.25	
Ref #297	**644E50300**	**PAVEMENT MARKING, MISC.: EDGE LINE, 5", YELLOW, (1343 FT)**		
	Awd	$1.75	$2,350.25	
Ref #298	**644E50300**	**PAVEMENT MARKING, MISC.: LANE LINE, 5", (1343 FT)**		
	Awd	$1.15	$1,544.45	
Ref #299	**644E50300**	**PAVEMENT MARKING, MISC.: STOP LINE, 20", WHITE, (72 FT)**		
	Awd	$12.00	$864.00	
Ref #300	**647E21012**	**SPEED MEASUREMENT MARKING, TYPE B125, (8 EACH)**		
	Awd	$435.00	$3,480.00	
Ref #301	**807E12010**	**WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, , (0.87 MILE)**		
	Awd	$19,325.00	$16,812.75	
Ref #302	**807E12110**	**WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, , (1.06 MILE)**		
	Awd	$11,134.00	$11,802.04	
Ref #303	**807E13010**	**WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKIN, (33.88 MILE)**		
	Awd	$2,815.00	$95,372.20	
Ref #304	**807E13110**	**WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKIN, (39.83 MILE)**		
	Awd	$1,765.00	$70,299.95	
Ref #305	**807E13310**	**WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKIN, (12993 FT)**		
	Awd	$2.40	$31,183.20	
Ref #306	**807E13410**	**WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKIN, (14600 FT)**		
	Awd	$1.75	$25,550.00	
Ref #307	**807E13430**	**WET REFLECTIVE SPRAY THERMOPLASTIC PAVEMENT MARKIN, (5419 FT)**		
	Awd	$2.10	$11,379.90	
Ref #308	**850E10010**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHAL, (73.71 MILE)**		
	Awd	$2,510.00	$185,012.10	
Ref #309	**850E10110**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHAL, (14600 FT)**		
	Awd	$1.35	$19,710.00	
Ref #310	**850E10130**	**GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHA, (18412 FT)**		
	Awd	$1.80	$33,141.60	
Ref #311	**850E20010**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRE, (1.93 MILE)**		
	Awd	$8,970.00	$17,312.10	
Ref #721	**630E81021**	**CONCRETE MEDIAN BARRIER SIGN BRACKET, AS PER PLAN, (30 EACH)**		
	Awd	$600.00	$18,000.00	
Ref #722	**630E97700**	**SIGNING, MISC.:CONCRETE BARRIER MOUNTED SIGN SUPPO, (4 EACH)**		
	Awd	$1,250.00	$5,000.00	

Section 8 - TRAFFIC CONTROL - Totals

Awd **$3,188,570.90**

Ref #312	**625E25402**	**CONDUIT, 2", 725.05, (36 FT)**	
	Awd	$1,520.00	$54,720.00
Ref #313	**625E25502**	**CONDUIT, 3", 725.05, (22360 FT)**	
	Awd	$5.60	$125,216.00
Ref #314	**625E25900**	**CONDUIT, JACKED OR DRILLED, 3", (1566 FT)**	
	Awd	$141.00	$220,806.00
Ref #315	**625E25920**	**CONDUIT, MISC.: 2-3" CONDUIT BANK, CONCRETE ENCASE, (724 FT)**	
	Awd	$28.40	$20,561.60
Ref #316	**625E25920**	**CONDUIT, MISC.: 3" FIBERGLASS CONDUIT ATTACHED TO , (408 FT)**	
	Awd	$57.00	$23,256.00
Ref #317	**625E29100**	**TRENCH, 36" DEEP, (8509 FT)**	
	Awd	$12.00	$102,108.00
Ref #318	**625E30710**	**PULL BOX, 725.08, 32", (27 EACH)**	
	Awd	$2,500.00	$67,500.00
Ref #319	**625E31500**	**MEDIAN PULL BOX, (9 EACH)**	
	Awd	$2,300.00	$20,700.00
Ref #320	**625E31510**	**PULL BOX REMOVED, (17 EACH)**	
	Awd	$235.00	$3,995.00
Ref #321	**632E29900**	**MESSENGER WIRE, 7 STRAND, 1/4" DIAMETER WITH ACCES, (6479 FT)**	
	Awd	$3.30	$21,380.70
Ref #322	**632E62810**	**INTERCONNECT CABLE, MISC.: AERIAL FIBER OPTIC INST, (6479 FT)**	
	Awd	$3.25	$21,056.75
Ref #323	**632E62810**	**INTERCONNECT CABLE, MISC.: UNDERGROUND FIBER OPTIC, (18866 FT)**	
	Awd	$2.50	$47,165.00
Ref #324	**632E70400**	**CONDUIT RISER, 2" DIAMETER, (2 EACH)**	
	Awd	$1,615.00	$3,230.00
Ref #325	**632E89300**	**WOOD POLE, CLASS 7, 35', (29 EACH)**	
	Awd	$1,100.00	$31,900.00
Ref #326	**804E15050**	**FIBER OPTIC CABLE, 288 FIBER AS PER PLAN, (22879 FT)**	
	Awd	$2.40	$54,909.60
Ref #327	**804E35001**	**FUSION SPLICE, AS PER PLAN, (1728 EACH)**	
	Awd	$22.60	$39,052.80
Ref #328	**804E37001**	**SPLICE ENCLOSURE, AS PER PLAN, (5 EACH)**	
	Awd	$1,630.00	$8,150.00
Ref #329	**804E98000**	**FIBER OPTIC CABLE, MISC.: REROUTED, (1250 FT)**	
	Awd	$10.00	$12,500.00

Section 9 - TRAFFIC SURVEILLANCE - Totals

Awd **$878,207.45**

Ref #330	**625E00450**	**CONNECTION, FUSED PULL APART, (2 EACH)**	
	Awd	$122.00	$244.00

Ref #331	**625E00460**	**CONNECTION, UNFUSED PULL APART, (2 EACH)**	
	Awd	$122.00	$244.00
Ref #332	**625E00480**	**CONNECTION, UNFUSED PERMANENT, (2 EACH)**	
	Awd	$122.00	$244.00
Ref #333	**625E22990**	**NO. 6 AWG 600 VOLT DISTRIBUTION CABLE, (12321 FT)**	
	Awd	$2.40	$29,570.40
Ref #334	**625E23000**	**NO. 4 AWG 600 VOLT DISTRIBUTION CABLE, (1512 FT)**	
	Awd	$3.20	$4,838.40
Ref #335	**625E23100**	**NO. 2 AWG 600 VOLT DISTRIBUTION CABLE, (1641 FT)**	
	Awd	$4.00	$6,564.00
Ref #337	**625E23308**	**DISTRIBUTION CABLE, MISC.: 1 CONDUCTOR, NO. 1/0 AW, (783 FT)**	
	Awd	$4.30	$3,366.90
Ref #338	**625E23308**	**DISTRIBUTION CABLE, MISC.: 1 CONDUCTOR, NO. 12 AWG, (435 FT)**	
	Awd	$1.35	$587.25
Ref #339	**625E23308**	**DISTRIBUTION CABLE, MISC.: 1 CONDUCTOR, NO. 3 AWG, (1092 FT)**	
	Awd	$2.80	$3,057.60
Ref #340	**625E25400**	**CONDUIT, 2", 725.04, (109 FT)**	
	Awd	$25.90	$2,823.10
Ref #341	**625E25408**	**CONDUIT, 2", 725.051, (2326 FT)**	
	Awd	$7.60	$17,677.60
Ref #342	**625E25908**	**CONDUIT, JACKED OR DRILLED, 725.052, 2", (175 FT)**	
	Awd	$107.00	$18,725.00
Ref #343	**625E25909**	**CONDUIT, JACKED OR DRILLED, 725.052, AS PER PLAN, , (162 FT)**	
	Awd	$112.00	$18,144.00
Ref #344	**625E29010**	**TRENCH, 30" DEEP, (4103 FT)**	
	Awd	$8.50	$34,875.50
Ref #345	**625E29931**	**MEDIAN JUNCTION BOX, AS PER PLAN, (28 EACH)**	
	Awd	$2,300.00	$64,400.00
Ref #346	**625E29940**	**BARRIER JUNCTION BOX, (7 EACH)**	
	Awd	$2,300.00	$16,100.00
Ref #347	**625E30700**	**PULL BOX, 725.08, 18", (20 EACH)**	
	Awd	$1,640.00	$32,800.00
Ref #348	**625E30706**	**PULL BOX, 725.08, 24", (1 EACH)**	
	Awd	$1,800.00	$1,800.00
Ref #349	**625E30710**	**PULL BOX, 725.08, 32", (22 EACH)**	
	Awd	$2,900.00	$63,800.00
Ref #350	**625E30730**	**PULL BOX, 725.08, 48", TYPE 1, (7 EACH)**	
	Awd	$3,740.00	$26,180.00
Ref #351	**625E31511**	**PULL BOX REMOVED, AS PER PLAN, (1 EACH)**	
	Awd	$237.00	$237.00
Ref #352	**625E32001**	**GROUND ROD, AS PER PLAN, (41 EACH)**	
	Awd	$207.00	$8,487.00
Ref #353	**625E34000**	**POWER SERVICE, (3 EACH)**	
	Awd	$11,000.00	$33,000.00
Ref #354	**625E34001**	**POWER SERVICE, AS PER PLAN, (2 EACH)**	
	Awd	$13,460.00	$26,920.00

Ref #355	**625E75550**	**DISTRIBUTION CABLE REMOVED, (160 FT)**		
	Awd	$1.50	$240.00	
Ref #356	**625E98000**	**LIGHTING, MISC.: STEP-DOWN TRANSFORMER AND SUPPORT, (2 EACH)**		
	Awd	$15,625.00	$31,250.00	
Ref #357	**630E70021**	**OVERHEAD SIGN SUPPORT, DMS TRUSS, 115', AS PER PLA, (1 EACH)**		
	Awd	$105,000.00	$105,000.00	
Ref #358	**630E70045**	**OVERHEAD SIGN SUPPORT, DMS PEDESTAL, AS PER PLAN, (1 EACH)**		
	Awd	$42,000.00	$42,000.00	
Ref #359	**630E70051**	**CATWALK, DMS TRUSS, AS PER PLAN, (1 EACH)**		
	Awd	$40,000.00	$40,000.00	
Ref #360	**630E70061**	**CATWALK, DMS PEDESTAL, AS PER PLAN, (1 EACH)**		
	Awd	$28,500.00	$28,500.00	
Ref #361	**630E70080**	**OVERHEAD SIGN SUPPORT FOUNDATION, DMS TRUSS, (1 EACH)**		
	Awd	$30,000.00	$30,000.00	
Ref #362	**630E70082**	**OVERHEAD SIGN SUPPORT FOUNDATION, DMS PEDESTAL, (1 EACH)**		
	Awd	$12,500.00	$12,500.00	
Ref #363	**631E92001**	**SIGN FLASHER ASSEMBLY, AS PER PLAN, (1 EACH)**		
	Awd	$24,860.00	$24,860.00	
Ref #364	**631E97700**	**SIGN LIGHTING MISC.: MODIFICATION TO FIRE ALARM SY, (1 EACH)**		
	Awd	$24,200.00	$24,200.00	
Ref #365	**632E90030**	**REMOVAL OF MISCELLANEOUS TRAFFIC SIGNAL ITEM: AERI, (130 FT)**		
	Awd	$1.90	$247.00	
Ref #366	**633E67201**	**CONTROLLER WORK PAD, AS PER PLAN, (8 EACH)**		
	Awd	$1,410.00	$11,280.00	
Ref #367	**638E07001**	**10" STEEL PIPE ENCASEMENT, BORED OR JACKED, AS PER, (62 FT)**		
	Awd	$646.00	$40,052.00	
Ref #368	**804E15031**	**FIBER OPTIC CABLE, 72 FIBER, AS PER PLAN, (43467 FT)**		
	Awd	$2.10	$91,280.70	
Ref #369	**804E37700**	**FIBER OPTIC CABLE TESTING, (LUMP SUM)**		
	Awd	$5,400.00	$5,400.00	
Ref #370	**809E21000**	**MICRO-DUCT PATHWAY, HYBRID, 3 ? 14/10 AND 3 ? 1.25, (13752 FT)**		
	Awd	$9.85	$135,457.20	
Ref #371	**809E24000**	**CONDUIT, MULTICELL, JACKED OR DRILLED 2", (1395 FT)**		
	Awd	$85.00	$118,575.00	
Ref #372	**809E25000**	**CONDUIT, MULTICELL, MISC.: 4", (453 FT)**		
	Awd	$20.50	$9,286.50	
Ref #373	**809E60040**	**CCTV IP-CAMERA SYSTEM, QUAD MULTI-VIEW FIXED WITH , (6 EACH)**		
	Awd	$9,345.00	$56,070.00	
Ref #374	**809E61002**	**CCTV CONCRETE POLE, 70 FEET, (4 EACH)**		
	Awd	$46,460.00	$185,840.00	
Ref #375	**809E61090**	**CCTV LOWERING UNIT, (5 EACH)**		
	Awd	$12,500.00	$62,500.00	
Ref #376	**809E63000**	**DYNAMIC MESSAGE SIGN (DMS), FULL-SIZE WALK-IN, (2 EACH)**		
	Awd	$109,600.00	$219,200.00	
Ref #377	**809E65000**	**ITS CABINET - GROUND MOUNTED, (5 EACH)**		
	Awd	$17,600.00	$88,000.00	

Ref #378	**809E65020**	**ITS CABINET - POWER DISTRIBUTION CABINET (PDC), (1 EACH)**	
	Awd	$12,300.00	$12,300.00
Ref #379	**809E65040**	**ITS CABINET - DMS, (2 EACH)**	
	Awd	$19,000.00	$38,000.00
Ref #380	**809E65990**	**ITS DEVICE, MISC.: CCTV POLE, 70' CONCRETE, REMOVE, (1 EACH)**	
	Awd	$14,700.00	$14,700.00
Ref #381	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF ANTENNA, (4 EACH)**	
	Awd	$645.00	$2,580.00
Ref #382	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF CCTV CAMERA, (3 EACH)**	
	Awd	$120.00	$360.00
Ref #383	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF CCTV LOWERING UNIT, (1 EACH)**	
	Awd	$1,800.00	$1,800.00
Ref #384	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF CONDUIT RISER, (1 EACH)**	
	Awd	$245.00	$245.00
Ref #385	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF POLE MOUNTED CABINET, (2 EACH)**	
	Awd	$500.00	$1,000.00
Ref #386	**809E65990**	**ITS DEVICE, MISC.: REMOVAL OF POLE MOUNTED DISCONN, (1 EACH)**	
	Awd	$220.00	$220.00
Ref #387	**809E65990**	**ITS DEVICE, MISC.: REMOVE AND RE-INSTALL ITS CABIN, (1 EACH)**	
	Awd	$5,250.00	$5,250.00
Ref #388	**809E70000**	**MAINTAINING ITS DURING CONSTRUCTION, (LUMP SUM)**	
	Awd	$37,300.00	$37,300.00

Section 10 - TRAFFIC SIGNALS - Totals

Awd	**$1,890,179.15**

Ref #389	**614E11110**	**LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSIST, (1000 HOUR)**	
	Awd	$95.00	$95,000.00
Ref #390	**614E11630**	**INCREASED BARRIER DELINEATION, (22500 FT)**	
	Awd	$0.46	$10,350.00
Ref #391	**614E12380**	**WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UN, (100 EACH)**	
	Awd	$1,850.00	$185,000.00
Ref #392	**614E12420**	**DETOUR SIGNING, (LUMP SUM)**	
	Awd	$29,000.00	$29,000.00
Ref #393	**614E12484**	**WORK ZONE INCREASED PENALTIES SIGN, (25 EACH)**	
	Awd	$620.00	$15,500.00
Ref #394	**614E12500**	**REPLACEMENT SIGN, (20 EACH)**	
	Awd	$350.00	$7,000.00
Ref #395	**614E12600**	**REPLACEMENT DRUM, (200 EACH)**	
	Awd	$58.00	$11,600.00
Ref #396	**614E12801**	**WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN, (4353 EACH)**	
	Awd	$38.00	$165,414.00
Ref #397	**614E13310**	**BARRIER REFLECTOR, TYPE 1 (ONE WAY), (1940 EACH)**	
	Awd	$6.00	$11,640.00
Ref #398	**614E13312**	**BARRIER REFLECTOR, TYPE 2 (ONE WAY), (45 EACH)**	
	Awd	$21.40	$963.00

Ref #399	**614E13350**	**OBJECT MARKER, ONE WAY, (1985 EACH)**	
	Awd	$17.00	$33,745.00
Ref #400	**614E18601**	**PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN, (46 SNMT)**	
	Awd	$640.00	$29,440.00
Ref #401	**614E20056**	**WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT, (25.75 MILE)**	
	Awd	$1,300.00	$33,475.00
Ref #402	**614E20100**	**WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT, (0.26 MILE)**	
	Awd	$1,500.00	$390.00
Ref #403	**614E22056**	**WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT, (43.31 MILE)**	
	Awd	$2,755.00	$119,319.05
Ref #404	**614E22100**	**WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT, (0.51 MILE)**	
	Awd	$2,500.00	$1,275.00
Ref #405	**614E23110**	**WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAI, (60396 FT)**	
	Awd	$1.40	$84,554.40
Ref #406	**614E23200**	**WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAIN, (500 FT)**	
	Awd	$2.00	$1,000.00
Ref #407	**614E24102**	**WORK ZONE DOTTED LINE, CLASS I, 6", 807 PAINT, (12114 FT)**	
	Awd	$1.00	$12,114.00
Ref #408	**615E10000**	**ROADS FOR MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$38,200.00	$38,200.00
Ref #409	**615E20000**	**PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, (222 SY)**	
	Awd	$358.00	$79,476.00
Ref #410	**615E20001**	**PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER , (1757 SY)**	
	Awd	$73.00	$128,261.00
Ref #411	**615E25001**	**PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B, AS PER , (3000 SY)**	
	Awd	$35.00	$105,000.00
Ref #412	**615E25001**	**PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B, AS PER , (4000 SY)**	
	Awd	$75.00	$300,000.00
Ref #413	**616E10000**	**WATER, (460 MGAL)**	
	Awd	$95.00	$43,700.00
Ref #414	**622E41050**	**PORTABLE BARRIER, "Y" CONNECTOR, (6 EACH)**	
	Awd	$725.00	$4,350.00
Ref #415	**622E41100**	**PORTABLE BARRIER, UNANCHORED, (103442 FT)**	
	Awd	$8.00	$827,536.00
Ref #416	**642E01312**	**LANE REDUCTION ARROW, TYPE 1, (4 EACH)**	
	Awd	$250.00	$1,000.00
Ref #417	**808E18700**	**DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY, (265 SNMT)**	
	Awd	$470.00	$124,550.00
Ref #418	**829E00100**	**WORK ZONE EGRESS WARNING SYSTEM, (77 SNMT)**	
	Awd	$1,015.00	$78,155.00
Ref #723	**614E20560**	**WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT, (40.89 MILE)**	
	Awd	$568.00	$23,225.52
Ref #724	**614E22360**	**WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT, (34.75 MILE)**	
	Awd	$825.00	$28,668.75
Ref #725	**614E23690**	**WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 P, (12993 FT)**	
	Awd	$0.75	$9,744.75

Ref #726	**614E24612**	**WORK ZONE DOTTED LINE, CLASS III, 6", 642 PAINT, (14600 FT)**	
	Awd	$0.60	$8,760.00
Ref #727	**614E24618**	**WORK ZONE DOTTED LINE, CLASS III, 12", 642 PAINT, (5419 FT)**	
	Awd	$0.75	$4,064.25

Section 11 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$2,651,470.72**

Ref #419	**509E10000**	**EPOXY COATED REINFORCING STEEL, (37067 LB)**	
	Awd	$1.60	$59,307.20
Ref #420	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (100 LB)**	
	Awd	$2.60	$260.00
Ref #421	**510E10000**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, (2495 EACH)**	
	Awd	$17.50	$43,662.50
Ref #422	**511E46012**	**CLASS QC1 CONCRETE WITH QC/QA, RETAINING/WINGWALL , (305 CY)**	
	Awd	$710.00	$216,550.00
Ref #423	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (1683 SY)**	
	Awd	$25.00	$42,075.00
Ref #424	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (629 SF)**	
	Awd	$4.50	$2,830.50
Ref #425	**516E14600**	**STRUCTURAL JOINT OR JOINT SEALER, MISC.: HOT APPLI, (1158 FT)**	
	Awd	$2.25	$2,605.50
Ref #426	**516E14600**	**STRUCTURAL JOINT OR JOINT SEALER, MISC.: HOT APPLI, (1214 FT)**	
	Awd	$2.25	$2,731.50

Section 12 - RETAINING WALLS - Totals

Awd	**$370,022.20**

Ref #427	**202E11201**	**PORTIONS OF STRUCTURE REMOVED, AS PER PLAN A, (LUMP SUM)**	
	Awd	$30,000.00	$30,000.00
Ref #428	**202E11201**	**PORTIONS OF STRUCTURE REMOVED, AS PER PLAN B, (LUMP SUM)**	
	Awd	$215,000.00	$215,000.00
Ref #429	**512E33010**	**TYPE 3 WATERPROOFING, (106 SY)**	
	Awd	$32.00	$3,392.00

Section 13 - STRUCTURE OVER 20 FOOT SPAN - Totals

Awd	**$248,392.00**

Ref #430	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$325,000.00	$325,000.00
Ref #431	**509E10000**	**EPOXY COATED REINFORCING STEEL, (49372 LB)**	
	Awd	$1.55	$76,526.60
Ref #432	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (40 LB)**	
	Awd	$2.85	$114.00
Ref #433	**509E30020**	**NO. 4 GFRP DEFORMED BARS, (5346 FT)**	
	Awd	$1.40	$7,484.40

Ref #434	**510E10001**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS , (10 EACH)**	
	Awd	$16.45	$164.50
Ref #435	**511E34445**	**CLASS QC2 CONCRETE, BRIDGE DECK, AS PER PLAN, (147 CY)**	
	Awd	$1,650.00	$242,550.00
Ref #436	**511E34448**	**CLASS QC2 CONCRETE, BRIDGE DECK (PARAPET), (52 CY)**	
	Awd	$775.00	$40,300.00
Ref #437	**511E44110**	**CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING, (2 CY)**	
	Awd	$3,400.00	$6,800.00
Ref #438	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (379 SY)**	
	Awd	$27.00	$10,233.00
Ref #439	**512E44450**	**TYPE E WATERPROOFING, (11 SY)**	
	Awd	$58.50	$643.50
Ref #440	**513E10200**	**STRUCTURAL STEEL MEMBERS, LEVEL UF, (553 LB)**	
	Awd	$8.25	$4,562.25
Ref #441	**514E00060**	**FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, (65 SF)**	
	Awd	$100.00	$6,500.00
Ref #442	**514E00067**	**FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS P, (65 SF)**	
	Awd	$50.00	$3,250.00
Ref #443	**514E21001**	**FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER, (LUMP SUM)**	
	Awd	$9,000.00	$9,000.00
Ref #444	**514E27702**	**FIELD PAINTING, MISC.: EPOXY COATING REPAIR OF EX, (1014 EACH)**	
	Awd	$8.10	$8,213.40
Ref #446	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (27 SF)**	
	Awd	$11.25	$303.75
Ref #447	**516E14600**	**STRUCTURAL JOINT OR JOINT SEALER, MISC.: HOT APPL, (74 FT)**	
	Awd	$6.40	$473.60
Ref #702	**516E11901**	**HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, (34 FT)**	
	Awd	$970.00	$32,980.00

Section 14 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$775,099.00**

Ref #449	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$325,000.00	$325,000.00
Ref #450	**254E01010**	**PAVEMENT PLANING, PORTLAND CEMENT CONCRETE (1 1/2", (14 SY)**	
	Awd	$540.00	$7,560.00
Ref #451	**254E01010**	**PAVEMENT PLANING, PORTLAND CEMENT CONCRETE (1/4" T, (22 SY)**	
	Awd	$345.00	$7,590.00
Ref #452	**509E10000**	**EPOXY COATED REINFORCING STEEL, (55537 LB)**	
	Awd	$1.60	$88,859.20
Ref #453	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (40 LB)**	
	Awd	$2.85	$114.00
Ref #454	**509E30020**	**NO. 4 GFRP DEFORMED BARS, (5521 FT)**	
	Awd	$1.40	$7,729.40
Ref #455	**510E10001**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS , (10 EACH)**	
	Awd	$16.45	$164.50

Ref #456	**511E34445**	**CLASS QC2 CONCRETE, BRIDGE DECK, AS PER PLAN, (146 CY)**	
	Awd	$1,650.00	$240,900.00
Ref #457	**511E34448**	**CLASS QC2 CONCRETE, BRIDGE DECK (PARAPET), (53 CY)**	
	Awd	$775.00	$41,075.00
Ref #458	**511E44110**	**CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING, (3 CY)**	
	Awd	$3,150.00	$9,450.00
Ref #459	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (385 SY)**	
	Awd	$27.00	$10,395.00
Ref #460	**512E44450**	**TYPE E WATERPROOFING, (15 SY)**	
	Awd	$65.50	$982.50
Ref #461	**513E10200**	**STRUCTURAL STEEL MEMBERS, LEVEL UF, (554 LB)**	
	Awd	$8.25	$4,570.50
Ref #462	**514E00060**	**FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, (64 SF)**	
	Awd	$100.00	$6,400.00
Ref #463	**514E00067**	**FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS P, (64 SF)**	
	Awd	$50.00	$3,200.00
Ref #464	**514E21001**	**FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER, (LUMP SUM)**	
	Awd	$9,000.00	$9,000.00
Ref #465	**514E27702**	**FIELD PAINTING, MISC.: EPOXY COATING REPAIR OF EX, (1594 EACH)**	
	Awd	$8.45	$13,469.30
Ref #466	**516E10000**	**PREFORMED ELASTOMERIC COMPRESSION JOINT SEAL, (16 FT)**	
	Awd	$182.00	$2,912.00
Ref #468	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (26 SF)**	
	Awd	$11.70	$304.20
Ref #469	**516E14600**	**STRUCTURAL JOINT OR JOINT SEALER, MISC.: HOT APPL, (59 FT)**	
	Awd	$7.30	$430.70
Ref #471	**847E10201**	**SUPERPLASTICIZED DENSE CONCRETE OVERLAY, AS PER PL, (35 SY)**	
	Awd	$358.00	$12,530.00
Ref #472	**847E20201**	**SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE , (2 CY)**	
	Awd	$585.00	$1,170.00
Ref #473	**847E30000**	**TEST SLAB, (LUMP SUM)**	
	Awd	$3,300.00	$3,300.00
Ref #474	**847E50000**	**HAND CHIPPING, (2 SY)**	
	Awd	$250.00	$500.00
Ref #703	**516E11901**	**HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, (34 FT)**	
	Awd	$1,048.00	$35,632.00

Section 15 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$833,238.30**

Ref #475	**201E11001**	**CLEARING AND GRUBBING, AS PER PLAN, (LUMP SUM)**	
	Awd	$1,500.00	$1,500.00
Ref #476	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$225,000.00	$225,000.00
Ref #477	**202E22901**	**APPROACH SLAB REMOVED, AS PER PLAN, (34 SY)**	
	Awd	$600.00	$20,400.00

Ref #478	**503E11101**	**COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN, (LUMP SUM)**	
	Awd	$40,000.00	$40,000.00
Ref #479	**503E21301**	**UNCLASSIFIED EXCAVATION, AS PER PLAN, (LUMP SUM)**	
	Awd	$80,000.00	$80,000.00
Ref #480	**505E11100**	**PILE DRIVING EQUIPMENT MOBILIZATION, (LUMP SUM)**	
	Awd	$20,500.00	$20,500.00
Ref #484	**509E10000**	**EPOXY COATED REINFORCING STEEL, (67294 LB)**	
	Awd	$1.58	$106,324.52
Ref #485	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (792 LB)**	
	Awd	$1.58	$1,251.36
Ref #486	**509E25000**	**UNCOATED REINFORCING STEEL, (560 LB)**	
	Awd	$1.65	$924.00
Ref #487	**509E30020**	**NO. 4 GFRP DEFORMED BARS, (3713 FT)**	
	Awd	$1.40	$5,198.20
Ref #488	**510E10001**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS , (114 EACH)**	
	Awd	$48.25	$5,500.50
Ref #489	**511E34446**	**CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK, (133 CY)**	
	Awd	$1,700.00	$226,100.00
Ref #490	**511E34450**	**CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPE, (37 CY)**	
	Awd	$600.00	$22,200.00
Ref #491	**511E41012**	**CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, (12 CY)**	
	Awd	$1,565.00	$18,780.00
Ref #492	**511E44112**	**CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT NOT INCLUD, (69 CY)**	
	Awd	$1,525.00	$105,225.00
Ref #493	**511E46512**	**CLASS QC1 CONCRETE WITH QC/QA, FOOTING, (67 CY)**	
	Awd	$525.00	$35,175.00
Ref #494	**512E10050**	**SEALING OF CONCRETE SURFACES (NON-EPOXY), (246 SY)**	
	Awd	$13.00	$3,198.00
Ref #495	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (128 SY)**	
	Awd	$27.00	$3,456.00
Ref #496	**512E33000**	**TYPE 2 WATERPROOFING, (26 SY)**	
	Awd	$40.00	$1,040.00
Ref #497	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (5 SY)**	
	Awd	$18.00	$90.00
Ref #499	**513E20000**	**WELDED STUD SHEAR CONNECTORS, (1332 EACH)**	
	Awd	$5.60	$7,459.20
Ref #500	**514E00050**	**SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL, (203 SF)**	
	Awd	$100.00	$20,300.00
Ref #501	**514E00056**	**FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME, (203 SF)**	
	Awd	$80.00	$16,240.00
Ref #502	**514E00060**	**FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, (5133 SF)**	
	Awd	$12.00	$61,596.00
Ref #503	**514E00066**	**FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, (5133 SF)**	
	Awd	$6.50	$33,364.50
Ref #504	**514E00504**	**GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTUR, (1 MNHR)**	
	Awd	$150.00	$150.00

Ref #505	**514E10000**	**FINAL INSPECTION REPAIR, (2 EACH)**		
	Awd	$200.00	$400.00	
Ref #506	**516E11901**	**HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, (46 FT)**		
	Awd	$806.00	$37,076.00	
Ref #507	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (74 SF)**		
	Awd	$14.60	$1,080.40	
Ref #508	**516E44201**	**ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LO, (2 EACH)**		
	Awd	$2,900.00	$5,800.00	
Ref #509	**516E44301**	**ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LO, (2 EACH)**		
	Awd	$3,250.00	$6,500.00	
Ref #510	**516E44301**	**ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LO, (2 EACH)**		
	Awd	$2,400.00	$4,800.00	
Ref #511	**518E21200**	**POROUS BACKFILL WITH GEOTEXTILE FABRIC, (66 CY)**		
	Awd	$155.00	$10,230.00	
Ref #512	**518E40000**	**6" PERFORATED CORRUGATED PLASTIC PIPE, (40 FT)**		
	Awd	$19.25	$770.00	
Ref #513	**518E40010**	**6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDI, (17 FT)**		
	Awd	$21.30	$362.10	
Ref #514	**519E11101**	**PATCHING CONCRETE STRUCTURE, AS PER PLAN, (32 SF)**		
	Awd	$178.00	$5,696.00	
Ref #516	**526E25010**	**REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=1, (132 SY)**		
	Awd	$330.00	$43,560.00	
Ref #517	**526E90010**	**TYPE A INSTALLATION, (48 FT)**		
	Awd	$240.00	$11,520.00	
Ref #518	**601E20001**	**CRUSHED AGGREGATE SLOPE PROTECTION, AS PER PLAN, (50 SY)**		
	Awd	$50.00	$2,500.00	
Ref #704	**513E10280**	**STRUCTURAL STEEL MEMBERS, LEVEL 4, (42400 LB)**		
	Awd	$8.50	$360,400.00	

Section 16 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$1,551,666.78**

Ref #481	**AB1**	**507E00500**	**12" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVE, (1050 FT)**	
		Awd	$20.70	$21,735.00
Ref #515	**AB1**	**523E20000**	**DYNAMIC LOAD TESTING(ALTERNATE 1), (3 EACH)**	
		Awd	$3,720.00	$11,160.00
Ref #705	**AB1**	**507E00550**	**12" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNI, (1190 FT)**	
		Awd	$47.00	$55,930.00
Ref #706	**AB1**	**507E93300**	**STEEL POINTS OR SHOES (ALTERNATE 1), (28 EACH)**	
		Awd	$1.00	$28.00

Section 17 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$88,853.00**

Ref #519	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
Awd	$225,000.00	$225,000.00	

Ref #520	**202E22901**	**APPROACH SLAB REMOVED, AS PER PLAN, (34 SY)**	
	Awd	$825.00	$28,050.00
Ref #521	**503E11100**	**COFFERDAMS AND EXCAVATION BRACING, (LUMP SUM)**	
	Awd	$135,000.00	$135,000.00
Ref #522	**503E21101**	**UNCLASSIFIED EXCAVATION, AS PER PLAN, (105 CY)**	
	Awd	$200.00	$21,000.00
Ref #523	**505E11100**	**PILE DRIVING EQUIPMENT MOBILIZATION, (LUMP SUM)**	
	Awd	$13,000.00	$13,000.00
Ref #527	**509E10000**	**EPOXY COATED REINFORCING STEEL, (57065 LB)**	
	Awd	$1.75	$99,863.75
Ref #528	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (96 LB)**	
	Awd	$4.00	$384.00
Ref #529	**509E25000**	**UNCOATED REINFORCING STEEL, (286 LB)**	
	Awd	$1.85	$529.10
Ref #530	**509E30020**	**NO. 4 GFRP DEFORMED BARS, (3764 FT)**	
	Awd	$1.40	$5,269.60
Ref #531	**510E10001**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS , (66 EACH)**	
	Awd	$71.60	$4,725.60
Ref #532	**511E32212**	**CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE, (163 CY)**	
	Awd	$1,650.00	$268,950.00
Ref #533	**511E34450**	**CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPE, (44 CY)**	
	Awd	$575.00	$25,300.00
Ref #534	**511E43212**	**CLASS QC1 CONCRETE WITH QC/QA, PIER, (12 CY)**	
	Awd	$2,585.00	$31,020.00
Ref #535	**511E43512**	**CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING , (25 CY)**	
	Awd	$1,250.00	$31,250.00
Ref #536	**512E10050**	**SEALING OF CONCRETE SURFACES (NON-EPOXY), (378 SY)**	
	Awd	$13.00	$4,914.00
Ref #537	**512E33000**	**TYPE 2 WATERPROOFING, (10 SY)**	
	Awd	$43.40	$434.00
Ref #538	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (61 SF)**	
	Awd	$8.70	$530.70
Ref #539	**518E21200**	**POROUS BACKFILL WITH GEOTEXTILE FABRIC, (9 CY)**	
	Awd	$133.00	$1,197.00
Ref #540	**519E11101**	**PATCHING CONCRETE STRUCTURE, AS PER PLAN, (17 SF)**	
	Awd	$180.00	$3,060.00
Ref #541	**523E20000**	**DYNAMIC LOAD TESTING, (3 EACH)**	
	Awd	$3,540.00	$10,620.00
Ref #542	**526E25010**	**REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=1, (180 SY)**	
	Awd	$350.00	$63,000.00
Ref #543	**526E90010**	**TYPE A INSTALLATION, (66 FT)**	
	Awd	$220.00	$14,520.00
Ref #544	**601E32201**	**ROCK CHANNEL PROTECTION, TYPE C WITH FILTER, AS PE, (90 CY)**	
	Awd	$175.00	$15,750.00
Ref #545	**846E00110**	**POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM, (25 CF)**	
	Awd	$715.00	$17,875.00

Section 18 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$1,021,242.75**

Ref #524	**AC1**	**507E00600**	**14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVE, (760 FT)**	
		Awd	$35.15	$26,714.00
Ref #526	**AC1**	**507E71200**	**SPECIAL - PILE ENCASEMENT (ALTERNATE 1), (155 FT)**	
		Awd	$90.50	$14,027.50
Ref #710	**AC1**	**507E00650**	**14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNI, (830 FT)**	
		Awd	$41.65	$34,569.50

Section 19 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-1 - Totals

Awd **$75,311.00**

Ref #546	**201E11001**	**CLEARING AND GRUBBING, AS PER PLAN, (LUMP SUM)**	
	Awd	$3,500.00	$3,500.00
Ref #547	**202E11203**	**PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, , (LUMP SUM)**	
	Awd	$300,000.00	$300,000.00
Ref #548	**202E22901**	**APPROACH SLAB REMOVED, AS PER PLAN, (68 SY)**	
	Awd	$500.00	$34,000.00
Ref #549	**503E11101**	**COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN, (LUMP SUM)**	
	Awd	$75,000.00	$75,000.00
Ref #550	**503E21101**	**UNCLASSIFIED EXCAVATION, AS PER PLAN, (416 CY)**	
	Awd	$175.00	$72,800.00
Ref #551	**505E11100**	**PILE DRIVING EQUIPMENT MOBILIZATION, (LUMP SUM)**	
	Awd	$14,300.00	$14,300.00
Ref #555	**509E10000**	**EPOXY COATED REINFORCING STEEL, (125924 LB)**	
	Awd	$1.60	$201,478.40
Ref #556	**509E20001**	**REINFORCING STEEL, REPLACEMENT OF EXISTING REINFOR, (580 LB)**	
	Awd	$1.85	$1,073.00
Ref #557	**509E25000**	**UNCOATED REINFORCING STEEL, (1308 LB)**	
	Awd	$1.60	$2,092.80
Ref #558	**509E30020**	**NO. 4 GFRP DEFORMED BARS, (6277 FT)**	
	Awd	$1.40	$8,787.80
Ref #559	**510E10001**	**DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS , (264 EACH)**	
	Awd	$34.50	$9,108.00
Ref #560	**511E34446**	**CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK, (221 CY)**	
	Awd	$1,500.00	$331,500.00
Ref #561	**511E34450**	**CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPE, (66 CY)**	
	Awd	$575.00	$37,950.00
Ref #562	**511E41012**	**CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, (19 CY)**	
	Awd	$1,830.00	$34,770.00
Ref #563	**511E44113**	**CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT NOT INCLUD, (159 CY)**	
	Awd	$1,525.00	$242,475.00
Ref #564	**511E46512**	**CLASS QC1 CONCRETE WITH QC/QA, FOOTING, (112 CY)**	
	Awd	$600.00	$67,200.00

Ref #565	**512E10050**	**SEALING OF CONCRETE SURFACES (NON-EPOXY), (335 SY)**	
	Awd	$13.00	$4,355.00
Ref #566	**512E10100**	**SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), (348 SY)**	
	Awd	$27.00	$9,396.00
Ref #567	**512E33000**	**TYPE 2 WATERPROOFING, (40 SY)**	
	Awd	$36.00	$1,440.00
Ref #568	**512E74000**	**REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACE, (20 SY)**	
	Awd	$18.00	$360.00
Ref #569	**513E10260**	**STRUCTURAL STEEL MEMBERS, LEVEL 3, (144000 LB)**	
	Awd	$5.00	$720,000.00
Ref #570	**513E20000**	**WELDED STUD SHEAR CONNECTORS, (2364 EACH)**	
	Awd	$5.25	$12,411.00
Ref #571	**514E00050**	**SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL, (460 SF)**	
	Awd	$100.00	$46,000.00
Ref #572	**514E00056**	**FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME, (460 SF)**	
	Awd	$80.00	$36,800.00
Ref #573	**514E00060**	**FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, (9040 SF)**	
	Awd	$10.00	$90,400.00
Ref #574	**514E00066**	**FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, (9040 SF)**	
	Awd	$5.50	$49,720.00
Ref #575	**514E00504**	**GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTUR, (2 MNHR)**	
	Awd	$150.00	$300.00
Ref #576	**514E10000**	**FINAL INSPECTION REPAIR, (2 EACH)**	
	Awd	$200.00	$400.00
Ref #577	**516E11901**	**HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, (97 FT)**	
	Awd	$790.00	$76,630.00
Ref #578	**516E13600**	**1" PREFORMED EXPANSION JOINT FILLER, (94 SF)**	
	Awd	$14.00	$1,316.00
Ref #579	**516E13900**	**2" PREFORMED EXPANSION JOINT FILLER, (9 SF)**	
	Awd	$12.75	$114.75
Ref #580	**516E44101**	**ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LO, (8 EACH)**	
	Awd	$2,390.00	$19,120.00
Ref #581	**516E44101**	**ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LO, (4 EACH)**	
	Awd	$3,300.00	$13,200.00
Ref #582	**518E21200**	**POROUS BACKFILL WITH GEOTEXTILE FABRIC, (124 CY)**	
	Awd	$110.00	$13,640.00
Ref #583	**518E40000**	**6" PERFORATED CORRUGATED PLASTIC PIPE, (94 FT)**	
	Awd	$19.75	$1,856.50
Ref #584	**518E40010**	**6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDI, (32 FT)**	
	Awd	$22.60	$723.20
Ref #585	**519E11101**	**PATCHING CONCRETE STRUCTURE, AS PER PLAN, (10 SF)**	
	Awd	$173.00	$1,730.00
Ref #587	**524E94802**	**DRILLED SHAFTS, 42" DIAMETER, ABOVE BEDROCK, (94 FT)**	
	Awd	$900.00	$84,600.00
Ref #588	**526E25010**	**REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=1, (264 SY)**	
	Awd	$350.00	$92,400.00

Ref #589		**526E90010**	**TYPE A INSTALLATION, (100 FT)**	
	Awd		$200.00	$20,000.00
Ref #590		**530E00200**	**SPECIAL - STRUCTURES, MISC.: PRECONSTRUCTION COND, (LUMP SUM)**	
	Awd		$1,400.00	$1,400.00
Ref #591		**530E00200**	**SPECIAL - STRUCTURES, MISC.: VIBRATION MONITORING, (LUMP SUM)**	
	Awd		$2,790.00	$2,790.00
Ref #592		**601E20000**	**CRUSHED AGGREGATE SLOPE PROTECTION, (80 SY)**	
	Awd		$55.00	$4,400.00
Ref #593		**601E20001**	**CRUSHED AGGREGATE SLOPE PROTECTION, AS PER PLAN, (26 SY)**	
	Awd		$125.00	$3,250.00
Ref #594		**848E10200**	**SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDR, (609 SY)**	
	Awd		$120.00	$73,080.00
Ref #595		**848E20000**	**SURFACE PREPARATION USING HYDRODEMOLITION, (609 SY)**	
	Awd		$165.00	$100,485.00
Ref #596		**848E30200**	**SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE , (11 CY)**	
	Awd		$290.00	$3,190.00
Ref #597		**848E50000**	**HAND CHIPPING, (20 SY)**	
	Awd		$300.00	$6,000.00
Ref #598		**848E50100**	**TEST SLAB, (LUMP SUM)**	
	Awd		$3,300.00	$3,300.00
Ref #599		**894E10000**	**THERMAL INTEGRITY PROFILING (TIP) TEST, (2 EACH)**	
	Awd		$4,900.00	$9,800.00

Section 20 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-2 - Totals

Awd **$2,940,642.45**

Ref #718	**AD2**	**507E00100**	**STEEL PILES HP10X42, FURNISHED(ALTERNATE 2), (2280 FT)**	
	Awd		$31.70	$72,276.00
Ref #719	**AD2**	**507E00150**	**STEEL PILES HP10X42, DRIVEN (ALTERNATE 2), (2090 FT)**	
	Awd		$15.90	$33,231.00
Ref #720	**AD2**	**507E93300**	**STEEL POINTS OR SHOES (ALTERNATE 2), (38 EACH)**	
	Awd		$121.25	$4,607.50

Section 21 - STRUCTURE OVER 20 FOOT SPAN (FRA-00161-2 - Totals

Awd **$110,114.50**

Ref #601	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
Awd		$345,000.00	$345,000.00
Ref #603	**111E10100**	**SPECIAL - DEPARTMENTS SHARE FACILITATED PARTNERING, (7750 EACH)**	
Awd		$1.00	$7,750.00
Ref #604	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
Awd		$1,791,250.00	$1,791,250.00
Ref #605	**619E16020**	**FIELD OFFICE, TYPE C, (24 MNTH)**	
Awd		$4,000.00	$96,000.00
Ref #606	**623E10000**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, (LUMP SUM)**	
Awd		$400,000.00	$400,000.00

Ref #607	**623E11000**	**PROVIDING ELECTRONIC INSTRUMENTATION, (LUMP SUM)**	
	Awd	$10,000.00	$10,000.00
Ref #608	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$1,600,000.00	$1,600,000.00
Ref #700	**108E10000**	**CPM PROGRESS SCHEDULE, (LUMP SUM)**	
	Awd	$25,000.00	$25,000.00

Section 22 - INCIDENTALS - Totals

Awd	**$4,275,000.00**