Ohio Department of Transportation
Official Bid Tabulation
Jack Marchbanks, Ph.D., Director

Project No. 240352
PID 111372
PER-CR 30/VAR-03.33/VAR (RESURF)
Federal
Type: TWO LANE RESURFACING
Letting Date: 6/27/2024
Completion Date: 10/31/2024

Contract Awarded To:	SHELLY COMPANY
Award Amount:	$1,996,455.98
Engineer's Estimate:	$2,065,000.00

Bidder 1
SHELLY COMPANY
80 PARK DR BOX 266
Perry
THORNVILLE, OH 43076
Bid $1,996,455.98

Ref #1	**254E01000**	**PAVEMENT PLANING, ASPHALT CONCRETE (DEPTH VARIES), (2249 SY)**	
	Awd	$9.50	$21,365.50

Section 1 - ROADWAY - Totals

Awd	**$21,365.50**

Ref #2	**407E10000**	**TACK COAT(0.05 GAL/SQ. YD.), (5886 GAL)**	
	Awd	$2.25	$13,243.50
Ref #3	**407E10000**	**TACK COAT(0.08 GAL/SQ. YD.), (9408 GAL)**	
	Awd	$2.25	$21,168.00
Ref #4	**441E50000**	**ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG, (4145 CY)**	
	Awd	$209.50	$868,377.50
Ref #5	**441E50000**	**ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG, (77 CY)**	
	Awd	$209.50	$16,131.50
Ref #6	**441E50000**	**ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG, (159 CY)**	
	Awd	$209.50	$33,310.50
Ref #7	**441E50200**	**ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448, (3320 CY)**	
	Awd	$209.50	$695,540.00
Ref #8	**617E10100**	**COMPACTED AGGREGATE, (1007 CY)**	
	Awd	$84.00	$84,588.00
Ref #9	**690E98800**	**SPECIAL - SPECIAL-HAULING PAVEMENT PLANING MATERIA, (117 TON)**	
	Awd	$40.00	$4,680.00

Section 2 - PAVEMENT - Totals

Awd	**$1,737,039.00**

Ref #10	**644E00400**	**CHANNELIZING LINE, 8", (380 FT)**	
	Awd	$2.25	$855.00
Ref #11	**644E00500**	**STOP LINE, (120 FT)**	
	Awd	$7.90	$948.00
Ref #12	**644E00700**	**TRANSVERSE/DIAGONAL LINE, (1220 FT)**	
	Awd	$7.25	$8,845.00
Ref #13	**648E00100**	**EDGE LINE, 4", (18.28 MILE)**	
	Awd	$1,356.00	$24,787.68
Ref #14	**648E00300**	**CENTER LINE, (9.14 MILE)**	
	Awd	$2,370.00	$21,661.80

Section 3 - TRAFFIC CONTROL - Totals

Awd	**$57,097.48**

Ref #15	**614E12460**	**WORK ZONE MARKING SIGN, (222 EACH)**	
	Awd	$98.00	$21,756.00
Ref #16	**614E13000**	**ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, (10 CY)**	
	Awd	$180.00	$1,800.00
Ref #17	**614E21400**	**WORK ZONE CENTER LINE, CLASS II, (18.28 MILE)**	
	Awd	$350.00	$6,398.00

Section 4 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$29,954.00**

Ref #18	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$7,500.00	$7,500.00
Ref #19	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$100,000.00	$100,000.00
Ref #20	**623E10001**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER P, (LUMP SUM)**	
	Awd	$3,500.00	$3,500.00
Ref #21	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$40,000.00	$40,000.00

Section 5 - INCIDENTALS - Totals

Awd	**$151,000.00**