Ohio Department of Transportation
Official Bid Tabulation
Pamela Boratyn, Director

Project No. 250291
PID 100349
WYA-US 23-00.00/04.03
Federal
Type: FOUR LANE RESURFACING
Letting Date: 5/22/2025
Completion Date: 11/15/2025

Contract Awarded To: KOKOSING CONSTRUCTION COMPANY INC
Award Amount: $3,478,615.65

Engineer's Estimate: $3,852,000.00

Bidder 1
KOKOSING CONSTRUCTION COMPANY INC
6235 WESTERVILLE RD
Franklin
WESTERVILLE, OH 43081
Bid $3,478,615.65

Bidder 2
SHELLY & SANDS INC
1515 HARMON AVE
Franklin
COLUMBUS, OH 43223
Bid $3,510,411.90

Ref #1	**832E30000**	**EROSION CONTROL, (1000 EACH)**	
	Awd	$1.00	$1,000.00
	2	$1.00	$1,000.00

Section 1 - EROSION CONTROL - Totals

Awd	**$1,000.00**
2	**$1,000.00**

Ref #2	**253E02000**	**PAVEMENT REPAIR, (300 CY)**	
	Awd	$460.00	$138,000.00
	2	$375.00	$112,500.00
Ref #3	**254E01000**	**PAVEMENT PLANING, ASPHALT CONCRETE, 1.5" DEPTH, (250802 SY)**	
	Awd	$0.70	$175,561.40
	2	$0.95	$238,261.90
Ref #4	**254E01600**	**PATCHING PLANED SURFACE, (5016 SY)**	
	Awd	$1.25	$6,270.00
	2	$4.00	$20,064.00
Ref #5	**407E20000**	**NON-TRACKING TACK COAT, (21318 GAL)**	
	Awd	$2.75	$58,624.50
	2	$3.25	$69,283.50
Ref #6	**442E00101**	**ANTI-SEGREGATION EQUIPMENT, AS PER PLAN, (7065 CY)**	
	Awd	$0.25	$1,766.25
	2	$10.00	$70,650.00
Ref #7	**442E10331**	**ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (, (10450 CY)**	
	Awd	$217.00	$2,267,650.00
	2	$210.00	$2,194,500.00
Ref #8	**617E10101**	**COMPACTED AGGREGATE, AS PER PLAN, (376 CY)**	
	Awd	$140.00	$52,640.00
	2	$100.00	$37,600.00
Ref #9	**618E40600**	**RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), (23.08 MILE)**	
	Awd	$605.00	$13,963.40
	2	$1,000.00	$23,080.00
Ref #10	**690E98400**	**SPECIAL - PAVER MOUNTED THERMAL PROFILING, (LUMP SUM)**	
	Awd	$3,500.00	$3,500.00
	2	$5,000.00	$5,000.00

Section 2 - PAVEMENT - Totals

Awd	**$2,717,975.55**
2	**$2,770,939.40**

Ref #11	**621E00100**	**RPM, (762 EACH)**	
	Awd	$35.25	$26,860.50
	2	$33.45	$25,488.90
Ref #12	**621E54000**	**RAISED PAVEMENT MARKER REMOVED, (762 EACH)**	
	Awd	$5.00	$3,810.00
	2	$2.00	$1,524.00
Ref #13	**644E00500**	**STOP LINE, (178 FT)**	
	Awd	$16.00	$2,848.00
	2	$16.00	$2,848.00

Ref #14	**807E11010**	**WET REFLECTIVE POLYESTER PAVEMENT MARKING, EDGE LI, (23.12 MILE)**	
	Awd	$2,960.00	$68,435.20
	2	$2,960.00	$68,435.20
Ref #15	**807E11110**	**WET REFLECTIVE POLYESTER PAVEMENT MARKING, LANE LI, (11.56 MILE)**	
	Awd	$2,080.00	$24,044.80
	2	$2,080.00	$24,044.80
Ref #16	**807E11310**	**WET REFLECTIVE POLYESTER PAVEMENT MARKING, CHANNEL, (412 FT)**	
	Awd	$1.70	$700.40
	2	$1.70	$700.40
Ref #17	**850E10011**	**GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHAL, (34.62 MILE)**	
	Awd	$1,820.00	$63,008.40
	2	$1,820.00	$63,008.40
Ref #18	**850E10130**	**GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHA, (412 FT)**	
	Awd	$1.65	$679.80
	2	$1.65	$679.80

Section 3 - TRAFFIC CONTROL - Totals

Awd	**$190,387.10**
2	**$186,729.50**

Ref #19	**614E11110**	**LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSIST, (120 HOUR)**	
	Awd	$100.00	$12,000.00
	2	$90.00	$10,800.00
Ref #20	**614E12460**	**WORK ZONE MARKING SIGN, (14 EACH)**	
	Awd	$150.00	$2,100.00
	2	$150.00	$2,100.00
Ref #21	**614E12484**	**WORK ZONE INCREASED PENALTIES SIGN, (10 EACH)**	
	Awd	$200.00	$2,000.00
	2	$200.00	$2,000.00
Ref #22	**614E12500**	**REPLACEMENT SIGN, (5 EACH)**	
	Awd	$192.00	$960.00
	2	$192.00	$960.00
Ref #23	**614E12600**	**REPLACEMENT DRUM, (50 EACH)**	
	Awd	$56.00	$2,800.00
	2	$56.00	$2,800.00
Ref #24	**614E18601**	**PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN, (6 SNMT)**	
	Awd	$850.00	$5,100.00
	2	$850.00	$5,100.00
Ref #25	**614E20056**	**WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT, (11.62 MILE)**	
	Awd	$1,550.00	$18,011.00
	2	$1,550.00	$18,011.00
Ref #26	**614E22056**	**WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT, (23.24 MILE)**	
	Awd	$2,950.00	$68,558.00
	2	$2,950.00	$68,558.00
Ref #27	**614E22326**	**WORK ZONE EDGE LINE, CLASS I, 6", 873, (1.49 MILE)**	
	Awd	$7,500.00	$11,175.00
	2	$15,000.00	$22,350.00

Ref #28	**614E23110**	**WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAI, (412 FT)**	
	Awd	$2.00	$824.00
	2	$2.00	$824.00
Ref #29	**808E18700**	**DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY, (42 SNMT)**	
	Awd	$850.00	$35,700.00
	2	$850.00	$35,700.00

Section 4 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$159,228.00**
2	**$169,203.00**

Ref #30	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$16,000.00	$16,000.00
	2	$15,000.00	$15,000.00
Ref #31	**614E11001**	**MAINTAINING TRAFFIC, AS PER PLAN, (LUMP SUM)**	
	Awd	$219,025.00	$219,025.00
	2	$252,540.00	$252,540.00
Ref #32	**623E10000**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, (LUMP SUM)**	
	Awd	$5,000.00	$5,000.00
	2	$15,000.00	$15,000.00
Ref #33	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$170,000.00	$170,000.00
	2	$100,000.00	$100,000.00

Section 5 - INCIDENTALS - Totals

Awd	**$410,025.00**
2	**$382,540.00**