Ohio Department of Transportation
Official Bid Tabulation
Pamela Boratyn, Director

Project No. 250491
PID 114386
GUE-/GUE-SR 93/SR 541/SR 658 VAR
Federal
Type: CHIP SEAL
Letting Date: 10/23/2025
Completion Date: 9/1/2026

Contract Awarded To: SHELLY COMPANY
Award Amount: $1,569,175.04

Engineer's Estimate: $1,527,000.00

Bidder 1
SHELLY COMPANY
80 PARK DR BOX 266
Perry
THORNVILLE, OH 43076
Bid $1,569,175.04

Bidder 2
MELWAY PAVING CO INC
7571 ST RT 83
Holmes
HOLMESVILLE, OH 44633
Bid $1,760,145.20

Ref #1	**202E30000**	**WALK REMOVED, (125 SF)**	
	Awd	$19.00	$2,375.00
	2	$10.00	$1,250.00
Ref #2	**608E10000**	**4" CONCRETE WALK, (125 SF)**	
	Awd	$72.50	$9,062.50
	2	$25.00	$3,125.00
Ref #3	**608E53020**	**DETECTABLE WARNING, (16 SF)**	
	Awd	$27.00	$432.00
	2	$20.00	$320.00

Section 1 - ROADWAY - Totals

Awd	**$11,869.50**
2	**$4,695.00**

Ref #4	**253E02000**	**PAVEMENT REPAIR, (250 CY)**	
	Awd	$535.00	$133,750.00
	2	$850.00	$212,500.00
Ref #5	**422E11001**	**AGGREGATE, SINGLE CHIP SEAL, TYPE A, AS PER PLAN, (311405 SY)**	
	Awd	$1.28	$398,598.40
	2	$1.40	$435,967.00
Ref #6	**422E25000**	**EMULSION, CHIP SEAL, (115221 GAL)**	
	Awd	$2.92	$336,445.32
	2	$3.30	$380,229.30
Ref #7	**886E11000**	**FOG SEAL, (46713 GAL)**	
	Awd	$2.85	$133,132.05
	2	$3.10	$144,810.30

Section 2 - PAVEMENT - Totals

Awd	**$1,001,925.77**
2	**$1,173,506.60**

Ref #8	**621E00100**	**RPM, (2829 EACH)**	
	Awd	$34.00	$96,186.00
	2	$40.00	$113,160.00
Ref #9	**621E54000**	**RAISED PAVEMENT MARKER REMOVED, (2829 EACH)**	
	Awd	$13.75	$38,898.75
	2	$20.00	$56,580.00
Ref #10	**630E03101**	**GROUND MOUNTED SUPPORT, NO. 3 POST, AS PER PLAN, (28 FT)**	
	Awd	$36.00	$1,008.00
	2	$12.00	$336.00
Ref #11	**630E80100**	**SIGN, FLAT SHEET, (16.5 SF)**	
	Awd	$60.00	$990.00
	2	$50.00	$825.00
Ref #12	**642E00104**	**EDGE LINE, 6", TYPE 1, (51.78 MILE)**	
	Awd	$755.00	$39,093.90
	2	$765.00	$39,611.70
Ref #13	**642E00300**	**CENTER LINE, TYPE 1, (25.89 MILE)**	
	Awd	$1,130.00	$29,255.70
	2	$1,000.00	$25,890.00

Ref #14	**642E00500**	**STOP LINE, TYPE 1, (72 FT)**	
	Awd	$8.00	$576.00
	2	$11.00	$792.00
Ref #15	**642E00620**	**CROSSWALK LINE, 12", TYPE 1, (98 FT)**	
	Awd	$8.00	$784.00
	2	$5.00	$490.00
Ref #16	**642E20802**	**YIELD LINE, TYPE 1, (20 FT)**	
	Awd	$6.50	$130.00
	2	$7.00	$140.00
Ref #17	**642E30000**	**REMOVAL OF PAVEMENT MARKING, (72 FT)**	
	Awd	$8.00	$576.00
	2	$3.00	$216.00
Ref #18	**642E30030**	**REMOVAL OF PAVEMENT MARKING, (76.86 MILE)**	
	Awd	$1,132.00	$87,005.52
	2	$1,070.00	$82,240.20

Section 3 - TRAFFIC CONTROL - Totals

Awd	**$294,503.87**
2	**$320,280.90**

Ref #19	**614E12460**	**WORK ZONE MARKING SIGN, (86 EACH)**	
	Awd	$86.00	$7,396.00
	2	$65.00	$5,590.00
Ref #20	**614E21550**	**WORK ZONE CENTER LINE, CLASS III, 642 PAINT, (77.67 MILE)**	
	Awd	$834.00	$64,776.78
	2	$810.00	$62,912.70
Ref #21	**614E26610**	**WORK ZONE STOP LINE, CLASS III, 642 PAINT, (216 FT)**	
	Awd	$5.57	$1,203.12
	2	$10.00	$2,160.00

Section 4 - MAINTENANCE OF TRAFFIC - Totals

Awd	**$73,375.90**
2	**$70,662.70**

Ref #22	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$4,500.00	$4,500.00
	2	$7,000.00	$7,000.00
Ref #23	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$165,000.00	$165,000.00
	2	$130,000.00	$130,000.00
Ref #24	**623E10000**	**CONSTRUCTION LAYOUT STAKES AND SURVEYING, (LUMP SUM)**	
	Awd	$3,000.00	$3,000.00
	2	$4,000.00	$4,000.00
Ref #25	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$15,000.00	$15,000.00
	2	$50,000.00	$50,000.00

Section 5 - INCIDENTALS - Totals

Awd	**$187,500.00**
2	**$191,000.00**