Ohio Department of Transportation
Official Bid Tabulation
Pamela Boratyn, Director

Project No. 250494
PID 112005
D10-General System GR FY2026
Federal
Type: GUARDRAIL REBUILDING
Letting Date: 10/23/2025
Completion Date: 10/1/2026

Contract Awarded To: PDK CONSTRUCTION INC
Award Amount: $2,243,023.00

Engineer's Estimate: $2,285,000.00

Bidder 1
PDK CONSTRUCTION INC
34070 CREW RD P O BOX 683
Meigs
POMEROY, OH 45769
Bid $2,243,023.00

Bidder 2
M P DORY CO
2001 INTEGRITY DR SOUTH
Franklin
COLUMBUS, OH 43209
Bid $2,419,388.75

Bidder 3
LAKE ERIE CONSTRUCTION COMPANY
25 NORWALK ROAD
Huron
NORWALK, OH 44857
Bid $2,428,125.00

Ref #1	**202E38101**	**GUARDRAIL REMOVED FOR STORAGE, AS PER PLAN, (88525 FT)**	
	Awd	$1.90	$168,197.50
	2	$1.80	$159,345.00
	3	$2.00	$177,050.00
Ref #2	**202E38500**	**BRIDGE RAILING REMOVED, (2087.5 FT)**	
	Awd	$1.80	$3,757.50
	2	$3.50	$7,306.25
	3	$2.40	$5,010.00
Ref #3	**202E38501**	**BRIDGE RAILING REMOVED, AS PER PLAN, (2512.5 FT)**	
	Awd	$1.60	$4,020.00
	2	$1.00	$2,512.50
	3	$6.00	$15,075.00
Ref #4	**606E15050**	**GUARDRAIL, TYPE MGS, (78325 FT)**	
	Awd	$16.30	$1,276,697.50
	2	$18.00	$1,409,850.00
	3	$17.60	$1,378,520.00
Ref #5	**606E15150**	**GUARDRAIL, TYPE MGS HALF POST SPACING, (1275 FT)**	
	Awd	$24.82	$31,645.50
	2	$26.00	$33,150.00
	3	$25.60	$32,640.00
Ref #6	**606E17360**	**GUARDRAIL, TYPE MGS, LONG-SPAN, (25 FT)**	
	Awd	$33.70	$842.50
	2	$30.00	$750.00
	3	$28.20	$705.00
Ref #7	**606E20050**	**ROUNDED END SECTION, (3 EACH)**	
	Awd	$55.00	$165.00
	2	$65.00	$195.00
	3	$75.00	$225.00
Ref #8	**606E25550**	**ANCHOR ASSEMBLY, MGS TYPE A, (230 EACH)**	
	Awd	$1,350.00	$310,500.00
	2	$1,250.00	$287,500.00
	3	$1,340.00	$308,200.00
Ref #9	**606E26150**	**ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016, (49 EACH)**	
	Awd	$2,200.00	$107,800.00
	2	$2,250.00	$110,250.00
	3	$2,400.00	$117,600.00
Ref #10	**606E26550**	**ANCHOR ASSEMBLY, MGS TYPE T, (46 EACH)**	
	Awd	$970.00	$44,620.00
	2	$1,000.00	$46,000.00
	3	$1,050.00	$48,300.00
Ref #11	**606E35140**	**BRIDGE TERMINAL ASSEMBLY, TYPE 4, (83 EACH)**	
	Awd	$550.00	$45,650.00
	2	$850.00	$70,550.00
	3	$750.00	$62,250.00
Ref #12	**606E50000**	**SPECIAL - RESHAPING BERM, (87700 FT)**	
	Awd	$0.05	$4,385.00
	2	$0.25	$21,925.00
	3	$0.10	$8,770.00

Section 1 - ROADWAY - Totals

Awd	**$1,998,280.50**
2	**$2,149,333.75**
3	**$2,154,345.00**

Ref #13	**626E00110**	**BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL, (1793 EACH)**	
	Awd	$10.00	$17,930.00
	2	$10.00	$17,930.00
	3	$10.00	$17,930.00

Section 2 - TRAFFIC CONTROL - Totals

Awd	**$17,930.00**
2	**$17,930.00**
3	**$17,930.00**

Ref #14	**517E72307**	**RAILING (DEEP BEAM RAIL WITH STEEL TUBULAR BACKUP , (2087.5 FT)**	
	Awd	$74.70	$155,936.25
	2	$80.00	$167,000.00
	3	$70.00	$146,125.00
Ref #15	**517E76200**	**RAILING FACED, (2512.5 FT)**	
	Awd	$10.10	$25,376.25
	2	$10.00	$25,125.00
	3	$10.00	$25,125.00

Section 3 - MISCELLANEOUS STRUCTURE - Totals

Awd	**$181,312.50**
2	**$192,125.00**
3	**$171,250.00**

Ref #16	**103E05000**	**PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYM, (LUMP SUM)**	
	Awd	$11,500.00	$11,500.00
	2	$20,000.00	$20,000.00
	3	$12,500.00	$12,500.00
Ref #17	**614E11000**	**MAINTAINING TRAFFIC, (LUMP SUM)**	
	Awd	$22,400.00	$22,400.00
	2	$15,000.00	$15,000.00
	3	$32,100.00	$32,100.00
Ref #18	**624E10000**	**MOBILIZATION, (LUMP SUM)**	
	Awd	$11,600.00	$11,600.00
	2	$25,000.00	$25,000.00
	3	$40,000.00	$40,000.00

Section 4 - INCIDENTALS - Totals

Awd	**$45,500.00**
2	**$60,000.00**
3	**$84,600.00**